

MSA, P.C.  
5033 Rouse Drive, Virginia Beach, VA 23462-3708  
Office (757) 490-9264 • Fax (757) 490-0634  
www.msaonline.com

Environmental Sciences • Planning • Surveying • Civil & Environmental Engineering • Landscape Architecture

July 14, 2014

Robert E. Smithson, Jr.  
Environmental Specialist Senior  
Virginia Department of Environmental Quality - TRO  
5636 Southern Boulevard  
Virginia Beach, Virginia 23462



**RE: VPA Application Review Comments**  
**Del Monte Fresh Production, Inc. - Permit No. VPA01057**  
**MSA Project #14068J**

Dear Mr. Smithson,

We have reviewed DEQ comments (6/26/14) to the VPA application package for the above-referenced facility. The following are responses listed in order to coincide with your comments. An original Form A signature Page is attached.

Form C

1. *Pages C.I.3-C.I.7.* New data will be provided as it becomes available.
2. *Page C-II.3, Item 7.* **Appendix B.** New data will be provided as it becomes available.
3. *Page C-II.2, Item 3* **Appendix C.** The revised Appendix C is attached and includes the spray field acreage in the text as well as being previously shown on the map unit legend.
4. *Page C-II.3, Item 8* **Appendix D.** Calculations will be provided when data becomes available.
5. *Hydraulic Loading Calculations – Appendix D.* Data used in the calculations was from most recent operation in 2011. As requested, new data will be provided when it becomes available.
6. *Nutrient Management Plan –* A NMP will be provided when it becomes available.

Please do not hesitate to contact me with any questions or clarification required on this project.

Sincerely,

Charles H. Hall, P.G., Hydrogeologist  
Director of Environmental Sciences

*Attachments*

## **TURF MAINTENANCE**

Tall fescue grass is maintained on the spray field. The grass cover provides uptake of potential nutrients in the spray water, increases evapotranspiration, and thus disposal of the water. The grass also provides erosion and sediment control to keep soils onsite. The grass and grass root matt also increase the detention time of the spray water in the topsoil where natural processes can attenuate nutrients. No specific yield is anticipated from the cover crop; as such, tissue testing is not required.

Table 1 provides a summary of field maintenance.

| Activity                     | Spring<br>(April) | Summer | Fall<br>(September) | Winter |
|------------------------------|-------------------|--------|---------------------|--------|
| Soils Sampling               | X                 |        | X                   |        |
| Aeration                     | X                 |        |                     |        |
| pH Amendment                 | X                 |        | X                   |        |
| Pesticide (Weed) Application | X                 |        |                     |        |
| Cutting                      | X                 | X      | X                   |        |
| Irrigation                   |                   | X      | X                   |        |
| Fertilizing                  |                   |        | X                   |        |
| Thatching                    |                   |        | X                   |        |
| Reseeding                    |                   |        | X                   |        |

Soils are tested bi-annually (in April and September). During the April sampling event the turf is evaluated with respect to weed coverage. When coverage exceeds 25%, weed control is prescribed in keeping with best management practices. Specific product will be determined based on plant materials found to be present. Application will be in keeping with product labeling and best management practices.

Application of wastewater and amendment may require the use of heavy equipment on the field. If compaction is observed, aeration is best conducted in the spring.

The soil pH at land application site shall be adjusted upward with lime, and if necessary downward with elemental sulfur, to achieve and maintain a pH range approximating 5.8 – 6.5 S.U.

Soil amendment with gypsum (calcium sulfate) at the rate of 10 to 15 lbs. per 100 sq. ft. shall be made on the spray application site in the spring if the Exchangeable Sodium Percentage (ESP) in the soil is equal to or greater than 15.

During the September sampling event the turf is evaluated with respect to health, density and thatch.

- If turf health is found to be substandard, amendments may be prescribed according to recommendations provided by A&L Eastern Laboratories, Inc. located in Richmond, Virginia. Amendments shall be applied according to recommendations

and best management practices. To prevent brown patch, nitrogen fertilizers shall be kept to a minimum.

- If turf is found to lack sufficient density, the field is reseeded as per recommendations for reseeding of established turfs.
- Generally it is not necessary to thatch fescue turf however if the thatch matt is found to be inhibiting water penetration thatching will be prescribed followed by reseeding at the specified rate for established turfs.

During the active growing season the turf is cut on a weekly basis to maintain a turf height of 2.5 - 4". Spray application is monitored to ensure adequate coverage. Consistent coverage and the prevention of wet spots along with management of nitrogen is the primary control for brown patch.

### **SPRAY FIELD LAND APPLICATION METHODS AND EQUIPMENT**

The method for land application of waste wash water used at this facility will be a piped spray irrigation system and supplemented by a truck mounted spreader rack if necessary. Upon the completion of each packing work day, 2,500 gallons per day can be sprayed to the field (Figure 5) through a piped spray irrigated system. The field contains a 50ft buffer around it. If needed, wastewater is transferred from the storage tanks to a 3,000 gallon capacity spray truck using the same 48gpm transfer pump. The spray field is 4.1 acres.


Each spray event will be applied to one of the spray field discharge lines. Each subsequent spray event will utilize the next sequential spray field discharge line such that the entire field will be covered over the span of 3 spray events. Application rates and active lines are adjusted by controller valves.

Over application is prevented by the operator visually inspecting and walking on the spray field to verify that the field appears dry enough to receive the wastewater. If the field appears to be wet, no spraying will be performed.

The irrigation system is reliable and has not had any major issues during operation in the past. The irrigation system will require onsite storage of additional piping, valves, controllers, and equipment for repair. In the event that a repair needs to be done to the spray irrigation system, the spray truck may be utilized to land apply wastewater along the same discharge lines. Application rates will be adjusted by speed of the spray trucks. Truck mounted spreader rack systems are very reliable for spray irrigation systems in that they are simple and have few parts. In the event that a spray truck becomes in need of repair, or during wet periods when spraying cannot occur, the 46,000 gallon storage capacity is used to hold excess wastewater until it can be applied. If the transfer pump goes down, one-half of the volume of the vertical storage tanks can still gravity drain into the trucks providing at least 23,000-gallons of holding capacity. For longer duration mechanical problems with the spray truck, a backup spray truck from another spray irrigation operation will be used. Since the spray field has excess capacity, the application rate can be increased so that the truck will have sufficient time between spray events.

**VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION  
FORM A  
ALL APPLICANTS**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering information, the information submitted is to the best of my knowledge and belief true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations. I further certify that I am an authorized signatory as specified in the VPA Permit Regulation (9VAC25-32).



|               |                         |                      |
|---------------|-------------------------|----------------------|
| Signature:    | <i>Paul J. Rice</i>     | Date: <i>5/30/14</i> |
| Printed Name: | Paul J. Rice            |                      |
| Title:        | S.R.V.P.U.A. Operations |                      |



# COMMONWEALTH of VIRGINIA

## DEPARTMENT OF ENVIRONMENTAL QUALITY

### TIDEWATER REGIONAL OFFICE

Molly Joseph Ward  
Secretary of Natural Resources

5636 Southern Boulevard, Virginia Beach, Virginia 23462  
(757) 518-2000 Fax (757) 518-2009  
[www.deq.virginia.gov](http://www.deq.virginia.gov)

David K. Paylor  
Director

Maria R. Nold  
Regional Director

June 26, 2014

Mr. Charles H. Hall, Director of Env. Sciences  
MSA, P.C.  
5033 Rouse Dr.  
Va. Beach, Va 23462-3708

RE: VPA 01057 Application from Del Monte Fresh Production, Inc. Processing Plant –  
Incomplete Application

Dear Charles:

The referenced application received June 10, 2014 has been reviewed for completeness and accuracy. Upon this review, we find that some additional information are required in order for us to deem the client's application complete and draft a permit. Please address the following items:

**Form A signature page appears to be a copy. DEQ requires the original signature of Mr. Rice. Sr. V.P. on this form.**

#### **Form C, Section C-I:**

Pages C.I.3 through C.I.7- As indicated, data are from 2011. Recent data are required when it becomes available. If not performed this summer, a special condition will be included in the permit which requires analysis of parameters found on these pages. Note: zinc, copper, magnesium, lead and possibly other parameters are marked believed absent which we know is not the case from previous sample events for this site.

#### **Form C, Section C-II.:**

Page C-II.3. Item#7: **Appendix B:** As indicated, data are from 2008. Recent data are required when it becomes available. If not performed this summer, a special condition will be included in the permit which requires analysis of parameters found on these pages. This applies to the cull fields as well.

Page C-II.2, Item#3: **Appendix C:** Number of acres of the wastewater spray field should be mentioned in this dialogue. Acres can only be found mentioned in the map unit legend.

Page C-II.3, Item#8: **Appendix D:** Land area determination/site life calculations- please provide these calculations (example attached) when data becomes available. If not provided this summer, a special condition will be included in the permit which requires analysis and calculation updates to this section.

Hydraulic Loading Calculations- **Appendix D:** As indicated, data are from 2011. Recent data are required when it becomes available. If not performed this summer, a special condition will be included in the permit which requires current information for these pages

Please provide a copy of a current, approved **nutrient management plan (NMP) for spray and cull fields when it will becomes available.** It should show, but not be limited to nutrient management details for applicable crops for each. We are particularly interested in discussions on sodium and copper residual levels in the field(s). Plan of action for problems (or potential problems) identified. Salts in irrigation water can be detrimental to plant growth if its concentration is too high, preventing water from being easily absorbed by the grass, causing drought-type symptoms. Tall Fescue is only moderately tolerant to salts. The plan should also recommend supplemental fertilizer in the summer to keep grasses healthy and viable, since the irrigation wastewater is generally nutrient poor. The plan will include, but not be limited to a discussion of PAN. The NMP should be approved by a certified nutrient mgt. planner.

**Please be aware that additional technical information *may* be required in order for us to draft your new VPA permit.**

Please make the necessary corrections and/or provide the additional information outlined above by **July 30, 2014, if possible.** Processing of your VPA Permit application will not begin until both our administrative and technical review are complete. Please **submit a revised original and one (1) copy to this office (extra copy unnecessary if it can be provided on disc.**

Good job on the application with what data you had. If you have any questions, please feel free to give me a call.

Sincerely,

Robert E. Smithson, Jr.  
Environmental Specialist Sr.

cc: DEQ ECM File  
Del Monte Fresh Production, J. D'Ottavio, V.P. Operations  
MSA – Morgan Evans



**MSA, P.C.**

5033 Rouse Drive, Virginia Beach, VA 23462-3708 • (757) 490-9264 • (757) 490-0634 [fax] • [www.msaonline.com](http://www.msaonline.com)  
Office in Hampton Roads  
Environmental Sciences • Planning • Surveying • Civil & Environmental Engineering • Landscape Architecture

---

June 10, 2014

Mark Sauer  
VPA Program  
Virginia Department of Environmental Quality  
5636 Southern Boulevard  
Virginia Beach, Virginia 23462



**RE: VPA Application**  
**Virginia Pollution Abatement Permit VPA01057**  
**Del Monte Fresh Production, Inc. - Processing Plant**  
**Mappsville, Virginia**  
**MSA Project #14068J**

Dear Mr. Sauer,

Thank you for your coordination assistance at the joint meeting between DEQ and VDH with the property Owner representatives. As agreed upon during that meeting, we are submitting an application package for the facilities' VPA permit to dispose wash water and tomato culls. Attached please find a completed application for the renewal of the existing VPA permit. Note that the Nutrient Management Plan for the spray and cull fields is currently being prepared by a certified NMP Planner. The plan will be forwarded to your office for inclusion with the application package as soon as it is completed.

Please understand that to expedite the review process, the Owner had already submitted an application fee (\$10,500) to the DEQ Receipts Control while the application package was being prepared. We understand now that since this permit is to be administratively continued, the Owner will be billed later for the annual permit maintenance fee. In that event, we presume that the submitted fee would be returned. Please do not hesitate to contact me if there are any questions regarding this application.

Sincerely,

Charles H. Hall, P.G., Hydrogeologist  
*Director of Environmental Sciences*

Copy: Del Monte Fresh Production

Attachment: Application Package

Permit Application Fee Form (and copy of submitted payment check)

Authorization to Bill Applicant for Public Notice

Permit Maintenance Fee Form

Section I

Virginia Pollution Abatement Application Form A

Section II

Virginia Pollution Abatement Application Form C

Section III

Appendices

Appendix A – Figures

Figure 1 – Site locations and Topographic Map

Figure 2 – Facility Schematic

Figure 3 – Site Features

Figure 4 – Land Application Methods

Figure 5 – Site Overview Map

Appendix B – Lab Results

Appendix C – Agronomic Practices

Appendix D – Calculations

Appendix E – Additional Notes

Appendix F – References



**VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION  
FORM A  
ALL APPLICANTS**

|                  |                  |   |
|------------------|------------------|---|
| 1. Facility      | Name             | Del Monte Fresh Production, Inc. Processing Plant |
|                  | County/City      | Accomack County                                   |
|                  | Address          | 15141 Finney Mason Drive, Bloxom, Virginia 23308  |
| 2. Owner         | Legal Name       | Del Monte Fresh Production, Inc.                  |
|                  | Mailing Address  | 3306 Sydney Road Plant City, FL 33566             |
|                  | Telephone Number | 813-752-5145 ext. 202                             |
|                  | Email address    | jdottavio@freshdelmonte.com                       |
| 3. Owner Contact | Name             | Joseph D'Ottavio                                  |
|                  | Title            | VP Operations NA S.E. Region                      |
|                  | Mailing Address  | 3306 Sydney Road Plant City, FL 33566             |
|                  | Telephone Number | 813-716-2745                                      |
|                  | Email address    | jdottavio@freshdelmonte.com                       |

4. Existing permits (e.g., VPA, VPDES; VWP, RCRA; UIC); other:

| Agency  | Permit Type                          | Permit Number |
|---------|--------------------------------------|---------------|
| VDEQ    | VPA                                  | VPA 01057     |
| VDH-ODW | Transient non community water supply | PWSID 3001551 |
| VDEQ    | GWP                                  | GW0047300     |
|         |                                      |               |

5. Nature of Business: The establishment is seasonally engaged in performing services on crops (tomatoes), subsequent to their harvest, with the intent of preparing them (via washing, disinfection and packaging) for further market distribution or processing.

|              |      |  |  |
|--------------|------|--|--|
| SIC Code(s): | 0723 |  |  |
|--------------|------|--|--|

6. Type of Waste:

(check box as appropriate)

Proposed

Existing

Animal Waste (complete Form B)

☐
☐

Industrial Waste (complete Form C)

☐
☒

Land Application of Municipal Effluent  
(complete Form D, Part I)

☐
☐

Land Application of Biosolids/Sewage Sludge  
(complete Form D, Part II)

☐
☐

Reclamation and/or Distribution of Reclaimed  
Wastewater (Application Addendum)

☐
☐

7. General Location Map:

**VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION  
FORM A  
ALL APPLICANTS**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering information, the information submitted is to the best of my knowledge and belief true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations. I further certify that I am an authorized signatory as specified in the VPA Permit Regulation (9VAC25-32).

|               |                           |       |                |
|---------------|---------------------------|-------|----------------|
| Signature:    | <i>Paulz Rice</i>         | Date: | <i>5/30/14</i> |
| Printed Name: | <i>Paul Rice</i>          |       |                |
| Title:        | <i>Sr. Vice President</i> |       |                |

**VIRGINIA POLLUTION ABATEMENT  
PERMIT APPLICATION**

**FORM C INDUSTRIAL  
WASTE**



**Department of Environmental Quality**

# VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION

## FORM C

### INDUSTRIAL WASTE

#### PART C-I General Information

1. Facility Name: Del Monte Fresh Production, Inc. Processing Plant

2. Source(s) of Waste

a. *Provide a narrative which explains your facility operations and how wastes are produced.*

Tomatoes are harvested and transported to the processing facility via 1,000 pound transport containers. The product is dumped, via hydraulic lift, from the containers into a wash flume. The wash flume is filled with groundwater from an onsite well. The water is further heated to the approximate temperature of the product and treated with sodium hypochlorite to a concentration of 150 ppm. Tomatoes are further rinsed, sorted graded and packaged for distribution. On average 15,000 gallons per day wash water was generated in 2011. Spent wash water is land applied.

b. *Attach a line drawing of the facility in block diagram for showing the manufacturing or processing operations and all points where wastes are produced.*

(See Appendix A – Figure 2)

c. *Explain how sewage from employees is handled (i.e., septic tank/drainfield, sanitary sewer etc.):*

All domestic sewage is directed to an onsite subsurface disposal field. The disposal field construction permit was approved by the local VDH field office on the following dates with corresponding permit ID number is: 93-100-1044 (Approved 6/29/1999), 99-100-0130 (Approved 2/17/1999), 99-100-0923 (Approved 7/9/2001), 99-100-0924 (Approved 7/9/2001), 99-100-0925 (Approved 7/9/2001).

d. Operational Parameters

Maximum hours/day of operation: 18 / hours per day  
Average hours/day of operation: 12 / per day of operation  
Days/week of operation: weather dependant 0 - 7  
Specific months of operation: June - November

3. Non-Hazardous Declaration

a. Statement for Plant Operations

Is any part of the manufacturing operations, plant processes or waste treatment facilities at these plant facilities under the purview of the "Virginia Hazardous Waste Management Regulations" or the "Virginia Solid Waste Management Regulations?"        Yes  
  X   No.

If Yes, please provide a brief explanation of the type of permit or requirements that apply.

NA

- b. For waste to be land applied, a responsible person, as defined by VR680-14-01, must sign the following statement.

I certify that the waste described in this application is non-hazardous and not regulated under the Resource Conservation and Recovery Act.

Paula Ricci  
(Signature of Owner)

Date 6/3/14

#### 4. Waste Characterization

- a. *Wastewater - Provide at least one analysis for each parameter. Upon review, additional analyses may be required by DEQ. The system has been inactive (zero discharge) since the end of the 2011 operating period. Concentrations provided are from July 2011 or otherwise noted (\*) derived from the 2002 permit renewal. Request for waiver from some parameter testing requirements in Appendix E.*

| <u>Parameter</u>                | <u>Concentration</u>        |         |
|---------------------------------|-----------------------------|---------|
| Flow to treatment               | <u>0.0151</u>               | MGD     |
| Flow to storage                 | <u>0.0151</u>               | MGD     |
| Vol. to treatment               | <u>0.286465</u>             | MG      |
| Vol. to storage                 | <u>0.286465</u>             | MG      |
| Vol. Land applied               | <u>0.286465</u>             | MG/year |
| BOD <sub>5</sub>                | <u>177.83 *</u>             | mg/l    |
| COD                             | <u>317.33 *</u>             | mg/l    |
| TOC                             | <u>245.5 *</u>              | mg/l    |
| TSS                             | <u>154.17 *</u>             | mg/l    |
| Percent Solids                  | <u>0.015 *</u>              | %       |
| PH                              | <u>6.35</u>                 | S.U.    |
| Alkalinity as CaCO <sub>3</sub> | <u>Request to be waived</u> | mg/l    |
| Nitrogen, (Nitrate)             | <u>1.35</u>                 | mg/l    |
| Nitrogen, (Ammonium)            | <u>0.38</u>                 | mg/l    |
| Nitrogen, (Total Kjeldahl)      | <u>15.05</u>                | mg/l    |
| Phosphorus, (Total)             | <u>4.10</u>                 | mg/l    |
| Potassium, (Total)              | <u>48.75</u>                | mg/l    |
| Sodium                          | <u>215</u>                  | mg/l    |

- b. *Sludge - Provide at least one analysis for each parameter. Upon review, additional analyses may be required by DEQ. NA*

| <u>Parameter</u>                   | <u>Concentration*</u> |       |
|------------------------------------|-----------------------|-------|
| Percent Solids                     |                       | %     |
| Volatile Solids                    |                       | %     |
| pH                                 |                       | S.U.  |
| Alkalinity as CaCO <sub>3</sub> ** |                       | mg/kg |
| Nitrogen (Nitrate)                 |                       | mg/kg |
| Nitrogen (Ammonium)                |                       | mg/kg |
| Nitrogen (Total Kjeldahl)          |                       | mg/kg |
| Phosphorous (Total)                |                       | mg/kg |
| Potassium (Total)                  |                       | mg/kg |
| Lead                               |                       | mg/kg |
| Cadmium                            |                       | mg/kg |
| Copper                             |                       | mg/kg |
| Nickel                             |                       | mg/kg |
| Zinc                               |                       | mg/kg |

\* Unless otherwise noted, report results on dry weight basis.

\*\* Lime treated sludges (10% or more lime by dry weight) should be analyzed for percent CaCO<sub>3</sub>.

- c. Provide a separate waste characterization listing for each wastewater and sludge generated at the facility. Insert "Yes" beside all parameters believed present and provide at least one analysis for each. Insert "No" beside all parameters believed not present. Indicate "NA" for any parameter already addressed in Item 4a. or 4b.

| <u>Parameter</u>              | <u>Believed Present</u><br>(yes or no) | <u>Concentration</u> |
|-------------------------------|--|----------------------|
| Sodium                        | N/A                                    |                      |
| Bromide                       | No                                     |                      |
| Total Residual                |  |                      |
| Chlorine                      | No                                     |                      |
| Fecal Coliform                | No                                     |                      |
| Fluoride                      | No                                     |                      |
| Oil & Grease                  | No                                     |                      |
| Total                         |  |                      |
| Radioactivity                 | No                                     |                      |
| Total Alpha                   | No                                     |                      |
| Total Beta                    | No                                     |                      |
| Total Radium                  | No                                     |                      |
| Total Radium 226              | No                                     |                      |
| Sulfate (as SO <sub>4</sub> ) | No                                     |                      |
| Sulfide (as S)                | No                                     |                      |
| Sulfite (as SO <sub>3</sub> ) | No                                     |                      |
| Surfactants                   | No                                     |                      |
| Total Aluminum                | No                                     |                      |
| Total Barium                  | No                                     |                      |
| Total Boron                   | No                                     |                      |
| Total Cobalt                  | No                                     |                      |
| Total Iron                    | No                                     |                      |
| Total Magnesium               | No                                     |                      |
| Total Molybdenum              | No                                     |                      |
| Total Manganese               | No                                     |                      |
| Total Tin                     | No                                     |                      |
| Total Titanium                | No                                     |                      |
| Total Antimony                | No                                     |                      |
| Total Arsenic                 | No                                     |                      |
| Total Beryllium               | No                                     |                      |
| Total Cadmium                 | No                                     |                      |
| Total Chromium                | No                                     |                      |
| Total Copper                  | No                                     |                      |
| Total Lead                    | No                                     |                      |
| Total Mercury                 | No                                     |                      |
| Total Nickel                  | No                                     |                      |
| Total Selenium                | No                                     |                      |
| Total Silver                  | No                                     |                      |
| Total Thallium                | No                                     |                      |
| Total Zinc                    | No                                     |                      |
| Total Cyanide                 | No                                     |                      |
| Total Phenols                 | No                                     |                      |
| Dioxin                        | No                                     |                      |
| Acrolein                      | No                                     |                      |

\*If the analysis is for sludge, report results on dry weight basis.

c. (Continued)

| <u>Parameter</u>                       | <u>Believed Present</u><br>(yes or no) | <u>Concentration</u> |
|--|--|----------------------|
| Acrylonitrile                          | No                                     |                      |
| Benzene                                | No                                     |                      |
| Bis(Chloromethyl)Ether                 | No                                     |                      |
| Bromoform                              | No                                     |                      |
| Carbon Tetrachloride                   | No                                     |                      |
| Chlorobenzene                          | No                                     |                      |
| Chlorodibromomethane                   | No                                     |                      |
| Chloroethane                           | No                                     |                      |
| 2-Chloroethylvinyl Ether               | No                                     |                      |
| Chloroform                             | No                                     |                      |
| Dichlorobromomethane                   | No                                     |                      |
| Dichlorodifluoromethane                | No                                     |                      |
| 1,1-Dichloroethane                     | No                                     |                      |
| 1,2-Dichloroethane                     | No                                     |                      |
| 1,1-Dichloroethylene                   | No                                     |                      |
| 1,2-Dichloropropane                    | No                                     |                      |
| 1,3-Dichloropropylene                  | No                                     |                      |
| Ethylbenzene                           | No                                     |                      |
| Methyl Bromide                         | No                                     |                      |
| Methyl Chloride                        | No                                     |                      |
| Methylene Chloride                     | No                                     |                      |
| 1,1,2,2-Tetrachlorethane               | No                                     |                      |
| Tetrachloroethylene                    | No                                     |                      |
| Toluene                                | No                                     |                      |
| 1,2-TransDichloroethylene <sup>1</sup> | No                                     |                      |
| 1,1,-Trichloroethane                   | No                                     |                      |
| 1,1,2,-Trichloroethane                 | No                                     |                      |
| Trichloroethylene                      | No                                     |                      |
| Trichlorofluoromethane                 | No                                     |                      |
| Vinyl Chloride                         | No                                     |                      |
| 2-Chlorophenol                         | No                                     |                      |
| 2,4-Dichlorophenol                     | No                                     |                      |
| 2,4-Dimethylpheno                      | No                                     |                      |
| 4,6-Dinitro-O-Cresol                   | No                                     |                      |
| 2,4-Dinitrophenol                      | No                                     |                      |
| 2-Nitrophenol                          | No                                     |                      |
| 4-Nitrophenol                          | No                                     |                      |
| P-Chlor-M-Cresol                       | No                                     |                      |
| Pentachlorophenol                      | No                                     |                      |
| Phenol                                 | No                                     |                      |
| 2,4,6-Trichlorophenol                  | No                                     |                      |
| Acenaphthene                           | No                                     |                      |
| Acenaphtylene                          | No                                     |                      |
| Acenaphtylene                          | No                                     |                      |
| Benzidine                              | No                                     |                      |
| Benzo(a)Athrane                        | No                                     |                      |
| Benzo(a)Pyrene                         | No                                     |                      |
| 3,4-Benzofluoranthene                  | No                                     |                      |
| Benzo(ghi) Perylene                    | No                                     |                      |
| Benzo(k)Fluoranthene                   | No                                     |                      |
| Bis(2-Chloroethoxy)Methane             | No                                     |                      |
| Bis(2-Chloroethyl) Ether               | No                                     |                      |
| Bis(2-Chloroisopropyl)Ether            | No                                     |                      |
| Bis(4-Bromophenyl Phenyl Ether         | No                                     |                      |
| Butyl Benzyl Phthalate                 | No                                     |                      |
| 4-Chlorophenyl Phenyl Ether            | No                                     |                      |
| 2-Chloronaphthalene                    | No                                     |                      |
| Chrysene                               | No                                     |                      |
| Dibenzo(a,h) Anthracene                | No                                     |                      |



c. (Continued)

| <u>Parameter</u>                             | <u>Believed Present</u><br>(yes or no) | <u>Concentration</u> |
|--|--|----------------------|
| 1,2-Dichlorobenzene                          | No                                     |                      |
| 1,3-Dichlorobenzene                          | No                                     |                      |
| 1,4-Dichlorobenzene                          | No                                     |                      |
| 3,3'-Dichlorobenzidine                       | No                                     |                      |
| Diethyl Phthalate                            | No                                     |                      |
| Dimethyl Phthalate                           | No                                     |                      |
| Di-N-Butyl Phthalate                         | No                                     |                      |
| 2,4-Dinitrotoluene                           | No                                     |                      |
| 2,6-Dinitrotoluene                           | No                                     |                      |
| Di-N-Octyl Phthalate                         | No                                     |                      |
| 1,2-Diphenylhydrazine(as<br>Azobenzene)      | No                                     |                      |
| Fluoranthene                                 | No                                     |                      |
| Fluorene                                     | No                                     |                      |
| Hexachlorobenzene                            | No                                     |                      |
| Hexachlorobutadiene                          | No                                     |                      |
| Hexachlorocyclopentadiene                    | No                                     |                      |
| Hexachloroethane                             | No                                     |                      |
| Indeno(1,2,3-cd)Pyrene                       | No                                     |                      |
| Isophorone                                   | No                                     |                      |
| Naphthalene                                  | No                                     |                      |
| Nitrobenzene                                 | No                                     |                      |
| N-Nitrosodimethylamine                       | No                                     |                      |
| N-Nitrosodi-N-Propylamine                    | No                                     |                      |
| N-Nitrosodiphenylamine                       | No                                     |                      |
| Phenanthrene                                 | No                                     |                      |
| Pyrene                                       | No                                     |                      |
| 1,2,4 - Trichlorobenzene                     | No                                     |                      |
| Aldrin                                       | Yes                                    | BDL < 0.011 ug/L     |
| ̑- BHC                                       | Yes                                    | BDL < 0.011 ug/L     |
| ̑- BHC                                       | Yes                                    | BDL < 0.011ug/L      |
| ̑- BHC                                       | Yes                                    | BDL <0.011 ug/L      |
| ̑- BHC                                       | Yes                                    | BDL <0.011ug/L       |
| Chlordane                                    | Yes                                    | BDL < 0.53 ug/L      |
| 4,4'- DDT                                    | Yes                                    | BDL <0.011 ug/L      |
| 4,4'- DDE                                    | Yes                                    | BDL <0.011 ug/L      |
| 4,4'- DDD                                    | Yes                                    | BDL <0.011 ug/L      |
| Dieldrin                                     | Yes                                    | BDL < 0.011ug/L      |
| ̑-Endosulfan ̑-                              | Yes                                    | 0.40 ug/L            |
| Endosulfan Sulfate                           | Yes                                    | 1.3 ug/L             |
| Endrin                                       | Yes                                    | BDL < 0.5 ug/L       |
| Endrin Aldehyde                              | Yes                                    | BDL < 0.0053 ug/L    |
| Heptachlor                                   | Yes                                    | BDL < 0.011 ug/L     |
| Heptachlor Epoxide                           | Yes                                    | BDL <0.011 ug/L      |
| PCB - 1242                                   | Yes                                    | BDL < 0.53 ug/L      |
| PCB - 1254                                   | No                                     |                      |
| PCB - 1221                                   | Yes                                    | BDL < 0.53 ug/L      |
| PCB - 1232                                   | Yes                                    | BDL < 0.53 ug/L      |
| PCB - 1248                                   | No                                     |                      |
| PCB - 1260                                   | No                                     |                      |
| PCB - 1016                                   | No                                     |                      |
| Toxaphene                                    | Yes                                    | BDL < 0.53 ug/L      |
| Chloromethane                                | No                                     |                      |
| Chlorpyrifos                                 | No                                     |                      |
| Demeton                                      | No                                     |                      |
| Dichloromethane                              | No                                     |                      |
| (2,4-dichlorophenoxy) acetic<br>acid (2,4-D) | No                                     |                      |
| Di-2-Ethylhexyl Phthalate                    | No                                     |                      |
| MBAS   | No                                     |                      |

## c. (Continued)

| <u>Parameter</u>  | <u>Believed Present</u><br>(yes or no) | <u>Concentration</u> |
|-------------------|--|----------------------|
| Lindane           | No                                     |                      |
| Hydrogen Sulfide  | No                                     |                      |
| Silvex            | No                                     |                      |
| Tributyltin       | No                                     |                      |
| Kepone            | No                                     |                      |
| Malathion         | No                                     |                      |
| Methoxychlor      | No                                     |                      |
| Mirex             | No                                     |                      |
| Monochlorobenzene | No                                     |                      |
| Parathion         | No                                     |                      |

- d. *Provide a separate waste characterization listing for each wastewater and sludge generated at the facility. List any additional parameters believed present in the spaces provided below and provide at least one analysis for each.*

[illegible]

- Briefly describe the design and provide a line drawing of the waste treatment facility which relates the various components of the treatment system including source(s), treatment unit(s), disposal alternatives, and flow estimates from the various process units.

Wastewater (expended wash flume water) containing sodium hypochlorite is conveyed to a series of three (3) 15,000-gallon storage tanks utilizing a transfer pump (**2 HP Goulds Model 3888**) operating at 200 GPM @ 27 feet of TDH from a wet well. Wastewater is mechanically screened of solids via one Everfilt gravity type, 100 mesh screen installed on top of storage tank No. 1. Wastewater is passed over the screen prior to discharge into the storage tanks. Filtered solids fall through a chute below the screen and into a collection bin. Once filled the bin is emptied into a distribution truck for hauling to the cull disposal field. The screened effluent is then pumped from the storage tanks to irrigation sprinklers for land application and treatment by the in-situ soil onsite. An average of approximately 15,400-gallons per day is generated. The 46,000 gallons of storage provides 3 days worth of detention time to allow the wastewater to settle solids and gas off free chlorine prior to field application. Wastewater is sequentially applied to each section of the land application site to ensure uniform coverage.

(See Appendix A: Figure 2, 3 and 4)

6. Indicate the number and type of waste storage facilities. If existing, indicate the volume; DEQ may require additional information upon review.

| No.                        | Existing<br>(Volume)  | Proposed |
|----------------------------|-----------------------|----------|
| _____ Earthen Storage Pond | _____                 | _____    |
| _____ Storage Pit          | _____                 | _____    |
| <u>3</u> Storage Tank      | <u>15,000 gallons</u> | _____    |
| _____ Anaerobic Lagoon     | _____                 | _____    |
| <u>2</u> Other             | <u>500 gallons</u>    | _____    |
|                            | _____                 | _____    |

7. Have the existing storage/treatment facilities identified in Item 5 and 6 above been previously approved by the Department of Environmental Quality?

Yes X No \_\_\_\_\_

*If yes, provide the date of the approval and proceed to Item 8.*

*Approval Date: June 15, 2004 - VPA # 01057*

*If no, provide information required by Items 9, 10, and 11.*

8. Have the previously approved facilities been altered or expanded?

Yes \_\_\_\_\_ No X

*If yes, it will be necessary to provide the information for such facilities, as required by Items 9 & 10, and 11.*

*If no, proceed to Item 12.*

9. Provide conceptual design for the treatment facilities including design approach used. Explain how ground water will be protected. Demonstration should include soil evaluation, geology, hydrology, and topography. The following information must be provided for each proposed facility identified in Item 6 above and for those existing facilities in Items 7 and 8 which have not been either previously approved or were altered: **N/A**

*a. Design calculations for volume (ft<sup>3</sup>) and estimated days of storage*

*b. Description of lining material and permeability*

*c. Plan and cross-sectional views*

*d. Depth to seasonal high water table and separation to permanent water table.*

10. Will the proposed waste storage/treatment facilities be located within the 100-year flood plain?  
\_\_\_\_\_ Yes \_\_\_\_\_ No. **N/A**

*If yes, what is the elevation of the 100-year flood plain and elevation of the proposed facilities. Also, how will the waste storage facilities be protected from flooding? (Flood elevation can be obtained from your local county zoning/planning department).*

*N/A*  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

11. Will the proposed or existing storage/treatment facilities receive any storm water runoff?  
\_\_\_\_\_ Yes **X** No.

*If yes, provide total area (square feet, acres, etc.) from which runoff will occur and indicate this area on the line drawing (Item 5). **N/A***

*Total area:* \_\_\_\_\_  
*Dimensions:* \_\_\_\_\_

12. Will any part of the waste generated at your facility be land applied? Yes **X** No \_\_\_\_\_. If yes, Part C-II must be completed.

# VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION

## FORM C

### INDUSTRIAL WASTE

#### PART C-II Land Application and Waste Handling Procedure

Facility Name: Del Monte Fresh Production, Inc. Processing Plant

*Items 1-12 pertain to the land application of industrial sludge/wastewater at frequent and infrequent rates. The applicant may request a waiver in writing for any of the required information if it is not pertinent to their operation.*

1. For each land application site provide a topographic map of sufficient scale (5 foot contour preferred) clearly showing the location of the following features within 0.25 mile of the site. Provide a legend with approximate scale. (See General Instructions for map requirements.)

(See Appendix A – Figures 1 + 3)

- a. *Proposed or existing ground water monitoring wells*
- b. *General direction of ground water movement*
- c. *Water wells, abandoned or operating*
- d. *Surface water*
- e. *Springs (N/A)*
- f. *Public water supply(s)(Two found)*
- g. *Sink holes (N/A)*
- h. *Underground and/or surface mines (N/A)*
- i. *Mine pool (or others) surface water dischargepoints (N/A)*
- j. *Mining spoil piles and mine dumps (N/A)*
- k. *Quarry(s) (N/A)*
- l. *Sand and gravel pits (N/A)*
- m. *m. Gas and oil wells (N/A)*
- n. *Diversion ditch(s) (N/A)*
- o. *Agricultural drainage ditch(s)*
- p. *Occupied dwellings, including industrial and commercial establishments*
- q. *Landfills or dumps (N/A)*
- r. *Other unlined impoundments (N/A)*
- s. *Septic tanks and drainfields*
- t. *Injection wells*
- u. *Rock outcrops (N/A)*
- v. *Soil boring or test pits locations (N/A)*
- w. *Subsurface drainage tile (N/A)*

2. For each land application site provide a site plan of sufficient detail to clearly show any landscape features, which will require buffer zones or may limit land application. Provide a legend and clearly mark the field boundaries and property lines. The following landscape features should be delineated. (See General Instructions for map requirements.) (See Appendix A – Figure 3)
  - a. *Drainageways*
  - b. *Rock outcrops*
  - c. *Sink holes*
  - d. *Drinking water wells and springs*
  - e. *Monitoring wells*
  - f. *Property lines*
  - g. *Roadways*
  - h. *Occupied dwellings*
  - i. *Slopes (greater than 8% by slope class)*
  - j. *Wet spots*
  - k. *Severe erosion (SCS designation)*
  - l. *Frequently flooded soils (SCS designation)*
  - m. *Surface waters*
3. Provide a complete description of agronomic practices for each crop to be grown, on field-by-field basis including a nutrient management program, soil and/or plant tissue testing, and the coordination of tillage practices, planting and harvesting schedules and timing of land application.

(See Appendix C)
4. Describe all land application methods and any equipment used in the process.

(See Appendix A - Figure 4 and Appendix C)
5. Provide a detailed soil survey map, preferably photographically based, with the field boundaries clearly marked. (A USDA-SCS soil survey map should be provided, if available.)

(See Appendix C)

Provide a detailed legend for each soil survey map which uses accepted USDA-SCS descriptions of the typifying pedon for each soil series (soil type). Complex associations may be described as a range of characteristics. Soil descriptions should include the following information.

- a. *Soil symbol*
- b. *Soil series, textural phase and slope class*
- c. *Depth to seasonal high water table*
- d. *Depth to bedrock*
- e. *Estimated productivity group (for the proposed crop rotation).*
- f. *Estimated infiltration rate (surface soil)*
- g. *Estimated permeability of most restrictive subsoil layer*

(See Appendix F)

6. Representative soil borings for frequent land application and fixed spray irrigations, (to no less than 5 ft. or to the water table) are to be conducted for the typifying pedon of each soil series (soil type) and the following data collected and tests performed. All results for infiltration and permeability tests should be enclosed. Provide information on the items below:

Land application is seasonal so this requirement is not required for this site.

- a. *Soil symbol*
- b. *Soil series, textural phase and slope class*
- c. *Depth to seasonal high water table*
- d. *Depth to bedrock (N/A)*
- e. *Estimated productivity group (for the proposed crop rotation).*
- f. *Estimated infiltration rate (surface soil)*
- g. *Estimated permeability of most restrictive subsoil layer*

7. Representative soil samples are to be collected for each major soil type and analyzed for the soil parameters indicated on Page C-II.6. Samples are to be taken at a depth of 0-6 in.

(See Appendix B)

8. Land Area Determination:

- a. *Land area requirements are to be calculated and justified for each of the parameters listed below:*

| <u>Parameters</u>                                 | <u>Method of Determining Required Area</u>                   |
|---|--|
| 1. <i>Nitrogen</i>                                | <i>Crop uptake, immobilization denitrification, leaching</i> |
| 2. <i>Phosphorus</i>                              | <i>Crop uptake, soil adsorption</i>                          |
| 3. <i>Potassium</i>                               | <i>Crop uptake</i>   |
| 4. <i>Sulfur</i>                                  | <i>Crop uptake, soil adsorption leaching</i>                 |
| 5. <i>Salts</i>                                   | <i>Sodium Adsorption Ratio (SAR), leaching</i>               |
| 6. <i>Carbon/Nitrogen Ratio</i>                   |  |
| 7. <i>Metals(Ni, Cu, Zn, Pb, Co, Cd or other)</i> | <i>Cumulative loading for site life</i>                      |
| 8. <i>Anions (As, B, Chlorides)</i>               | <i>Leaching, Soil Adsorption</i>                             |
| 9. <i>Calcium Carbonate Equivalency</i>           | <i>Soil pH management</i>                                    |
| 10. <i>Other Parameters</i>                       |  |
| <i>(As needed or as requested by DEQ)</i>         |  |

For each parameter and method of assimilation, (i.e. crop uptake, denitrification, immobilization, soil adsorption leaching, etc.), the required land area is to be justified by attaching calculations and appropriate references. Allowances for soil adsorption are to be justified by pertinent soil testing.

Provide calculations describing the nutrient value of the waste as lbs per dry ton or mg/l nitrogen (PAN), phosphorus ( $P_2O_5$ ), potassium ( $K_2O$ ), and any liming effects which may occur from land application.

b. Land area requirements for application of industrial wastewater or liquid sludge are to be determined and an annual water balance on a monthly basis developed integrating the following factors:

1. Monthly precipitation
2. Monthly evapotranspiration data
3. Soil percolation rates (from subsurface permeability data)
4. Monthly wastewater loading
5. Monthly storage requirement
6. Monthly storage input/drawdown

(See Appendix D)

9. Does the volume of wastewater generated as determined by the water balance in 8.b. exceed the hydraulic loading rate (inches/acre/year) of the soils? \_\_\_\_ Yes   X   No

*If Yes, explain how excess loading will be disposed of:*

---

---

---

---

---

---

---

---

10. Is the land application site owned by the applicant?   X   Yes \_\_\_\_ No.

*If No, answer question 11 and have the land owner complete the authorization form, Page C-II-5.*

11. Complete page C-II.5 by providing the name(s), address(es), site locations and signatures of non-applicant land owner on whose property industrial waste will be applied (A separate approval will be required for each additional owner.):

**N/A**



**AUTHORIZATION TO LAND APPLY WASTE**

(Land Owner must sign and date this approval)

*N/A*

As land owner, I authorize \_\_\_\_\_ to land apply wastewater/sludge to my property in accordance with their VPA Form C application. This authorization will remain in effect until such time as I notify the Department of Environmental Quality in writing that this authorization has been withdrawn.

Name: \_\_\_\_\_

Address: \_\_\_\_\_

\_\_\_\_\_

Telephone: \_\_\_\_\_

Site Location(s) \_\_\_\_\_

Date: \_\_\_\_\_

Signature: \_\_\_\_\_

# SOIL TEST PARAMETERS FOR LAND APPLICATION SITES<sup>(1)</sup>

| Parameter  | Sludge – Frequent below Agronomic Rates <sup>(2)</sup> | Sludge - Frequent at Agronomic Rates <sup>(3)</sup> | Sludge - Infrequent | Wastewater |
|--|--|---|---------------------|------------|
| Soil Organic Matter (%)                              |  | *   |                     | *          |
| Soil pH (Std. Units)                                 | *  | *   | *                   | *          |
| Cation Exchange Capacity (me/100g)                   | *  | *   | *                   | *          |
| Total Nitrogen (ppm)                                 |  | *   |                     | *          |
| Organic Nitrogen (ppm)                               |  | *   |                     | *          |
| Ammonia Nitrogen (ppm)                               |  | *   |                     | *          |
| Nitrate Nitrogen (ppm)                               |  | *   |                     | *          |
| Available Phosphorus (ppm)                           | *  | *   | *                   | *          |
| Exchangeable Potassium (mg/100g)                     | *  | *   | *                   |            |
| Exchangeable Sodium (mg/100g)                        |  | *   |                     | *          |
| Exchangeable Calcium (mg/100g)                       |  | *   |                     | *          |
| Exchangeable Magnesium (mg/100g)                     |  | *   |                     | *          |
| Copper (ppm)   |  | *   |                     | *          |
| Nickel (ppm)   |  | *   |                     | *          |
| Zinc (ppm)   |  | *   |                     | *          |
| Cadmium (ppm)  |  | *   |                     | *          |
| Lead (ppm)   |  | *   |                     | *          |
| Chromium (ppm)                                       |  | *   |                     | *          |
| Manganese (ppm)                                      |  | *   |                     | *          |
| Particle Size Analysis or USDA Textural Estimate (%) |  | *   |                     | *          |
| Hydraulic Conductivity (in/hr)                       |  |   |                     | *          |

<sup>(1)</sup> Unless otherwise stated, analyses shall be reported on a dry weight basis.


<sup>(2)</sup> Less than 70% of agronomic nitrogen rates (annual basis).

<sup>(3)</sup> Test requirements will be adjusted based on previous test results.

\* Test for these parameters.

# **APPENDIX A**

## Figures



Source: Bloxom and Hallwood, Virginia USGS Quadrangle Topographic Maps



FIGURE 1. SITE VICINITY MAP


**DEL MONTE PRODUCTION, INC. PROCESSING PLANT  
MAPPSVILLE, VIRGINIA**

|           |           |       |     |
|-----------|-----------|-------|-----|
| MSA JOB # | DATE:     | SCALE | By: |
| 14068J    | 4/19/2014 | NTS   | JEF |

**MSA. P.C.**



5033 Rouse Drive, Virginia Beach, VA. 23462  
(757) 490-9264 (ofc) (757) 490-0634 (fax)  
www.msaonline.com  
Environmental Sciences + Planning + Surveying  
Engineering + Landscape Architecture



**FIGURE 2. Wastewater Disposal Schematic**

**VPA PERMIT APPLICATION**  
**DEL MONTE PRODUCTION, INC. PROCESSING PLANT**  
**MAPPSVILLE, VIRGINIA**

MSA, P.C.  
 5033 Rouse Drive, Virginia Beach, VA. 23462  
 (757) 490-9264 (o) (757) 490-0634 (fax)  
 www.msonline.com  
 Environmental Sciences + Planning + Surveying  
 Civil and Environmental Engineering + Landscape Architecture

| MSA JOB # | DATE:     | SCALE |
|-----------|-----------|-------|
| 14068J    | 4/19/2014 | NTS   |




FIGURE 3 Site Features


**VPA PERMIT APPLICATION  
DEL MONTE PRODUCTION, INC. PROCESSING PLANT  
MAPPSVILLE, VIRGINIA**

MSA JOB#  
14068J


DATE:  
4/19/14


SCALE  
NTS


MSA, P.C.



5033 Rouse Drive, Virginia Beach, VA. 23462  
(757) 490-9264 (ofc) (757) 490-0634 (fax)  
www.msasonline.com  
Environmental Sciences + Planning + Surveying  
Engineering + Landscape Architecture



|  |  |   |  |                             |                            |                      |
|--|--|---|--|-----------------------------|----------------------------|----------------------|
| <p><b>FIGURE 4. LAND APPLICATION METHODS</b></p> <p><b>VPA PERMIT APPLICATION</b></p> <p><b>DEL MONTE PRODUCTION, INC. PROCESSING PLANT</b></p> <p><b>MAPPSVILLE, VIRGINIA</b></p> |  | <p>MSA. P.C. 5033 Rouse Drive, Virginia Beach, VA. 23462<br/>(757) 490-9264 (of) (757) 490-0634 (fax)<br/>www.msaonline.com<br/>Environmental Sciences + Planning + Surveying<br/>Civil and Environmental Engineering + Landscape Architecture</p> <p></p> |  | <p>MSA JOB #<br/>14068J</p> | <p>DATE:<br/>4/19/2014</p> | <p>SCALE<br/>NTS</p> |
|--|--|---|--|-----------------------------|----------------------------|----------------------|



Source: Web Soil Survey



**FIGURE 5. SITE OVERVIEW MAP**

**DEL MONTE PRODUCTION, INC. PROCESSING PLANT  
MAPPSVILLE, VIRGINIA**

|           |           |       |     |
|-----------|-----------|-------|-----|
| MSA JOB # | DATE:     | SCALE | By: |
| 14068J    | 4/19/2014 | NTS   | JEF |

**MSA, P.C.**



5033 Rouse Drive, Virginia Beach, VA. 23462  
(757) 490-9264 (ofc) (757) 490-0634 (fax)  
www.msaonline.com  
Environmental Sciences + Planning + Surveying  
Engineering + Landscape Architecture



## **APPENDIX B**

### Lab Results

**Land Application Site – Spray Field**  
**Soil Analytical Results**  
**(4-08-2008)**

System has been idle since 2011. Soil samples collected and reported from 2008 permit compliance requirements are utilized for application reference. Testing of complete Page C-II.6 parameters are being analyzed at this time. Soil analyses are expressed as dry weights in mg/kg.



LABORATORIES, INC.

MSA, P.C.  
Attn: Matt Reed  
5033 Rouse Drive  
Virginia Beach, VA 23462

### Analytical Summary

816 Kiwanis Street  
Hampton, Virginia 23661  
Phone 757 • 244 • 3424  
Fax 757 • 244 • 3243

Project No. : 99167  
Project Name : ECBP VPA  
Date Received: April 10, 2008  
Date Sampled : April 08, 2008  
Time Sampled : 12:00  
Date Issued : May 07, 2008


Lab # 1(A)/Sample ID : ECBP BS *BoDNE*

| Parameter                | Result | Units    | DL    | Date/Time Analyzed | Method             | Analyst |
|--------------------------|--------|----------|-------|--------------------|--------------------|---------|
| pH                       | 6.9    | SU       | --    | 04-24/1040         | SW9045D            | ETC     |
| Cation Exchange Capacity | 12     | meq/100g | --    | 05-01/1900         | SW9081             | ETC     |
| Exchangeable Potassium   | 122    | mg/kg    | --    | 04-28/1700         | Extractable Cation | ETC     |
| Exchangeable Sodium      | 3.1    | %        | 0.5   | 04-24/0938         | LA29BESP           | ETC     |
| Available Phosphorus     | 198    | mg/kg    | 50    | 04-24/1120         | BRAY-1P            | ETC     |
| TKN                      | 875    | mg/kg    | 0.5   | 04-24/0819         | 4500-NH3D          | ETC     |
| Nitrate (as N)           | 1.98   | mg/kg    | 0.982 | 04-29/0829         | 300.0              | ETC     |
| Nitrate+Nitrite-N        | 1.98   | mg/kg    | 0.982 | 04-29/0829         | SW9056             | ETC     |
| Total Nitrogen           | 877    | mg/kg    | 0.5   | 05-06/1324         | calc.              | ETC     |
| Soluble Salts            | 0.13   | mmhos/cm | 0.01  | 04-24/1231         | Soluble Salts 1:2  | ETC     |

Lab # 2(A)/Sample ID : ECBP UU *MUNDEN*

| Parameter                | Result | Units    | DL    | Date/Time Analyzed | Method             | Analyst |
|--------------------------|--------|----------|-------|--------------------|--------------------|---------|
| pH                       | 6.7    | SU       | --    | 04-24/1040         | SW9045D            | ETC     |
| Cation Exchange Capacity | 13     | meq/100g | --    | 05-01/1900         | SW9081             | ETC     |
| Exchangeable Potassium   | 132    | mg/kg    | --    | 04-28/1700         | Extractable Cation | ETC     |
| Exchangeable Sodium      | 3.6    | %        | 0.5   | 04-24/0938         | LA29BESP           | ETC     |
| Available Phosphorus     | 175    | mg/kg    | 50    | 04-24/1120         | BRAY-1P            | ETC     |
| TKN                      | 759    | mg/kg    | 0.5   | 04-24/0819         | 4500-NH3D          | ETC     |
| Nitrate (as N)           | 4.39   | mg/kg    | 0.896 | 04-29/0829         | 300.0              | ETC     |
| Nitrate+Nitrite-N        | 4.39   | mg/kg    | 0.896 | 04-29/0829         | SW9056             | ETC     |
| Total Nitrogen           | 763    | mg/kg    | 0.5   | 05-06/1324         | calc.              | ETC     |
| Soluble Salts            | 0.15   | mmhos/cm | 0.01  | 04-24/1231         | Soluble Salts 1:2  | ETC     |

BDL = Below Detection Limit

  
Anamarie E. McKinley  
Laboratory Manager  
H8421489-1

## **Wastewater Analytical Results (7-14-2011)**

System has been idle since 2011 and not currently producing wastewater. Water sample results from 7/2011 permit compliance requirements are utilized for application reference. Water analyses are expressed as mg/L.



Pace Analytical Services, Inc.  
205 East Meadow Road - Suite A  
Eden, NC 27288  
(336)623-8921

Pace Analytical Services, Inc.  
2225 Riverside Dr.  
Asheville, NC 28804  
(828)254-7176

Pace Analytical Services, Inc.  
9800 Kinsey Ave. Suite 100  
Huntersville, NC 28078  
(704)875-9092

## ANALYTICAL RESULTS

Project: **VPA 1057** *086300*

Pace Project No.: 9298369

Sample: VPA 1057-1 Lab ID: 9298369001 Collected: 07/14/11 12:35 Received: 07/15/11 13:40 Matrix: Water

| Parameters  | Results | Units | Report Limit | DF | Prepared       | Analyzed       | CAS No.    | Qual |
|---|---------|-------|--------------|----|----------------|----------------|------------|------|
| <b>608SF GCS Pesticides and PCBs</b> Analytical Method: EPA 608 |         |       |              |    |                |                |            |      |
| Aldrin  | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 309-00-2   |      |
| alpha-BHC   | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 319-84-6   |      |
| beta-BHC  | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 319-85-7   |      |
| delta-BHC   | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 319-86-8   |      |
| gamma-BHC (Lindane)   | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 58-89-9    |      |
| Chlordane (Technical)   | ND      | ug/L  | 0.53         | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 57-74-9    |      |
| 4,4'-DDD  | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 72-54-8    |      |
| 4,4'-DDE  | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 72-55-9    |      |
| 4,4'-DDT  | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 50-29-3    |      |
| Dieldrin  | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 60-57-1    |      |
| Endosulfan I  | 0.40    | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 959-98-8   |      |
| Endosulfan II   | 1.2     | ug/L  | 0.11         | 10 | 07/19/11 16:40 | 07/20/11 18:35 | 33213-65-9 |      |
| Endosulfan sulfate  | 1.3     | ug/L  | 0.11         | 10 | 07/19/11 16:40 | 07/20/11 18:35 | 1031-07-8  |      |
| Endrin  | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 72-20-8    |      |
| Endrin aldehyde   | ND      | ug/L  | 0.0053       | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 7421-93-4  |      |
| Heptachlor  | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 76-44-8    |      |
| Heptachlor epoxide  | ND      | ug/L  | 0.011        | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 1024-57-3  |      |
| PCB-1016 (Aroclor 1016)   | ND      | ug/L  | 0.53         | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 12674-11-2 |      |
| PCB-1221 (Aroclor 1221)   | ND      | ug/L  | 0.53         | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 11104-28-2 |      |
| PCB-1232 (Aroclor 1232)   | ND      | ug/L  | 0.53         | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 11141-16-5 |      |
| PCB-1242 (Aroclor 1242)   | ND      | ug/L  | 0.53         | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 53469-21-9 |      |
| PCB-1248 (Aroclor 1248)   | ND      | ug/L  | 0.53         | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 12672-29-6 |      |
| PCB-1254 (Aroclor 1254)   | ND      | ug/L  | 0.53         | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 11097-69-1 |      |
| PCB-1260 (Aroclor 1260)   | ND      | ug/L  | 0.53         | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 11096-82-5 |      |
| Toxaphene   | ND      | ug/L  | 0.53         | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 8001-35-2  |      |
| Tetrachloro-m-xylene (S)  | 158     | %     | 53-110       | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 877-09-8   | S2   |
| Decachlorobiphenyl (S)  | 55      | %     | 61-121       | 1  | 07/19/11 16:40 | 07/19/11 20:45 | 2051-24-3  | S1   |

### 200.7 MET ICP, Dissolved

Analytical Method: EPA 200.7 Preparation Method: EPA 200.7

|                   |     |      |      |   |                |                |           |  |
|-------------------|-----|------|------|---|----------------|----------------|-----------|--|
| Copper, Dissolved | 250 | ug/L | 5.0  | 1 | 07/19/11 15:05 | 07/20/11 11:49 | 7440-50-8 |  |
| Zinc, Dissolved   | 302 | ug/L | 10.0 | 1 | 07/19/11 15:05 | 07/20/11 02:19 | 7440-66-6 |  |

### 6010 MET ICP

Analytical Method: EPA 6010 Preparation Method: EPA 3010

|           |        |      |       |    |                |                |           |  |
|-----------|--------|------|-------|----|----------------|----------------|-----------|--|
| Calcium   | 44800  | ug/L | 100   | 1  | 07/20/11 10:20 | 07/21/11 13:56 | 7440-70-2 |  |
| Magnesium | 11600  | ug/L | 100   | 1  | 07/20/11 10:20 | 07/21/11 13:56 | 7439-95-4 |  |
| Potassium | 62900  | ug/L | 50000 | 10 | 07/20/11 10:20 | 07/21/11 14:14 | 7440-09-7 |  |
| Sodium    | 292000 | ug/L | 50000 | 10 | 07/20/11 10:20 | 07/21/11 14:14 | 7440-23-5 |  |

### 350.1 Ammonia

Analytical Method: EPA 350.1

|                   |     |      |      |   |  |                |           |  |
|-------------------|-----|------|------|---|--|----------------|-----------|--|
| Nitrogen, Ammonia | 7.5 | mg/L | 0.10 | 1 |  | 07/21/11 14:04 | 7664-41-7 |  |
|-------------------|-----|------|------|---|--|----------------|-----------|--|

### 351.2 Total Kjeldahl Nitrogen

Analytical Method: EPA 351.2

|                           |      |      |     |   |  |                |           |  |
|---------------------------|------|------|-----|---|--|----------------|-----------|--|
| Nitrogen, Kjeldahl, Total | 28.1 | mg/L | 2.5 | 5 |  | 07/17/11 12:36 | 7727-37-9 |  |
|---------------------------|------|------|-----|---|--|----------------|-----------|--|

### 353.2 Nitrogen, NO2/NO3 unpres

Analytical Method: EPA 353.2

|                   |    |      |      |   |  |                |  |  |
|-------------------|----|------|------|---|--|----------------|--|--|
| Nitrogen, Nitrate | ND | mg/L | 0.20 | 1 |  | 07/15/11 22:03 |  |  |
|-------------------|----|------|------|---|--|----------------|--|--|

Date: 08/02/2011 09:53 AM

## REPORT OF LABORATORY ANALYSIS

Page 4 of 17

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, Inc..



Pace Analytical Services, Inc.  
205 East Meadow Road - Suite A  
Eden, NC 27288  
(336)623-8921

Pace Analytical Services, Inc.  
2225 Riverside Dr.  
Asheville, NC 28804  
(828)254-7176

Pace Analytical Services, Inc.  
9800 Kincey Ave. Suite 100  
Huntersville, NC 28078  
(704)875-9092

## ANALYTICAL RESULTS

Project:

~~VPA 1057~~ 080302

Pace Project No.: 9298369

|                                |         |                                 |                           |                          |               |                |            |      |
|--------------------------------|---------|---------------------------------|---------------------------|--------------------------|---------------|----------------|------------|------|
| Sample: VPA 1057-1             |         | Lab ID: 9298369001              | Collected: 07/14/11 12:35 | Received: 07/15/11 13:40 | Matrix: Water |                |            |      |
| Parameters                     | Results | Units                           | Report Limit              | DF                       | Prepared      | Analyzed       | CAS No.    | Qual |
| 353.2 Nitrogen, NO2/NO3 unpres |         | Analytical Method: EPA 353.2    |                           |                          |               |                |            |      |
| Nitrogen, Nitrite              | 0.64    | mg/L                            | 0.10                      | 1                        |               | 07/15/11 22:03 |            |      |
| Nitrogen, NO2 plus NO3         | ND      | mg/L                            | 0.20                      | 1                        |               | 07/15/11 22:03 |            |      |
| 365.1 Phosphorus, Total        |         | Analytical Method: EPA 365.1    |                           |                          |               |                |            |      |
| Phosphorus                     | 6.7     | mg/L                            | 0.20                      | 4                        |               | 07/22/11 15:36 | 7723-14-0  |      |
| 4500 Chloride                  |         | Analytical Method: SM 4500-Cl-E |                           |                          |               |                |            |      |
| Chloride                       | 410     | mg/L                            | 75.0                      | 15                       |               | 07/19/11 10:51 | 16887-00-6 |      |

Date: 08/02/2011 09:53 AM

## REPORT OF LABORATORY ANALYSIS

Page 5 of 17

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, Inc..

# CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

|   |  |  |  |  |  |
|---|--|--|--|--|--|
| <b>Section A</b><br>Required Client Information:<br>Company: <u>HSA</u><br>Address: <u>5033 Rouse Dr</u><br>Email To: <u>LB, LN 23462</u><br>Phone: <u></u> Fax: <u></u><br>Requested Due Date/TAT: <u></u> |  | <b>Section B</b><br>Required Project Information:<br>Report To: <u>TOYI BACORRO</u><br>Copy To: <u></u><br>Purchase Order No.: <u>EAST COAST</u><br>Project Name: <u>VPA 1057</u><br>Project Number: <u>080306</u>   |  | <b>Section C</b><br>Invoice Information:<br>Attention: <u>SAM</u><br>Company Name: <u>SAM</u><br>Address: <u></u><br>Pace Quote Reference: <u></u><br>Pace Project Manager: <u></u><br>Pace Profile #: <u>3639-6</u> |  |
| Page: <u>1</u> of <u>2</u><br>1477732   |  | <b>REGULATORY AGENCY</b><br><input type="checkbox"/> NPDES <input type="checkbox"/> GROUND WATER <input type="checkbox"/> DRINKING WATER<br><input type="checkbox"/> UST <input type="checkbox"/> RCRA <input type="checkbox"/> OTHER <u></u><br>Site Location: <u></u> STATE: <u></u> |  |  |  |

| ITEM # | Section D<br>Required Client Information | Matrix Codes<br>MATRIX L CODE | SAMPLE TYPE (G=GRAB C=COMP) | COLLECTED       |                    | SAMPLE TEMP AT COLLECTION | # OF CONTAINERS | Preservatives | Analysis Test (Y/N) | Requested Analysis Filtered (Y/N) | Residual Chlorine (Y/N) | Pace Project No./ Lab I.D. |
|--------|--|-------------------------------|-----------------------------|-----------------|--------------------|---------------------------|-----------------|---------------|---------------------|-----------------------------------|-------------------------|----------------------------|
|        |  |                               |                             | COMPOSITE START | COMPOSITE END/GRAB |                           |                 |               |                     |                                   |                         |                            |
| 1      | VPA 1057-1                               | DW                            | WTC                         | DATE            | TIME               | DATE                      | TIME            |               |                     |                                   |                         |                            |
| 2      | -2                                       | WT                            |                             | 7/14/11         | 1235               | 7/14/11                   | 1235            |               |                     |                                   |                         |                            |
| 3      | -3                                       | WW                            |                             |                 | 1240               |                           |                 |               |                     |                                   |                         |                            |
| 4      | -4                                       | WP                            |                             |                 | 1245               |                           |                 |               |                     |                                   |                         |                            |
| 5      | -5                                       | P                             |                             |                 | 1250               |                           |                 |               |                     |                                   |                         |                            |
| 6      | -6                                       | SL/Solid                      |                             |                 | 1255               |                           |                 |               |                     |                                   |                         |                            |
| 7      | -7                                       | Oil                           |                             |                 | 1300               |                           |                 |               |                     |                                   |                         |                            |
| 8      |  | Wipe                          |                             |                 | 1305               |                           |                 |               |                     |                                   |                         |                            |
| 9      |  | Air                           |                             |                 |                    |                           |                 |               |                     |                                   |                         |                            |
| 10     |  | Tissue                        |                             |                 |                    |                           |                 |               |                     |                                   |                         |                            |
| 11     |  | Other                         |                             |                 |                    |                           |                 |               |                     |                                   |                         |                            |
| 12     |  |                               |                             |                 |                    |                           |                 |               |                     |                                   |                         |                            |

|   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
|---|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|
| <b>ADDITIONAL COMMENTS</b><br>23462<br>Pace Sample/Me 7/15/11 1340<br>Pace Sample/Me 7/15/11 1340                           |  |  |  | <b>RELINQUISHED BY / AFFILIATION</b><br>DATE<br>7/14/11 1200<br>7/15/11 1340 |  |  |  | <b>ACCEPTED BY / AFFILIATION</b><br>DATE<br>7/14/11 1247<br>7/15/11 1346 |  |  |  | <b>SAMPLE CONDITIONS</b><br>Received on Ice (Y/N)<br>Custody Sealed Cooler (Y/N)<br>Samples Intact (Y/N) |  |  |  |
| <b>SAMPLER NAME AND SIGNATURE</b><br>PRINT Name of SAMPLER: <u>TOYI BACORRO</u><br>SIGNATURE of SAMPLER: <u>[Signature]</u> |  |  |  |  |  |  |  |  |  |  |  | Temp in °C<br>3.4<br>3.4   |  |  |  |

ATTACHMENT C-1a  
DEPARTMENT OF ENVIRONMENTAL QUALITY  
Virginia Pollution Abatement Monitoring Report

Facility Name: East Coast Brokers and Packers, Incorporated  
Address: 15141 Finney Mason Road  
Mappsville, VA 23407

VPA Permit No.: VPA01057

Report Period: From 7 / 1 / 2011 To 7 / 31 / 2011

Monitoring Station: Spray Irrigation Wastewater From Storage Tank

| Parameters           | Units  |          | Monitoring Results |          | Analysis Frequency | Sample Type |
|----------------------|--------|----------|--------------------|----------|--------------------|-------------|
|                      |        |          | Average            | Maximum  |                    |             |
| Flow                 | MGD    | Reported | 0.0151             | 0.0340   | 1/Day              | Measured    |
|                      |        | Required | NL                 | NL       | 1/Day              | Measured    |
| Total Vol. Applied   | MG     | Reported |                    | 0.286465 | Monthly            | Calculated  |
|                      |        | Required | *****              | NL       | Monthly            | Calculated  |
| Application Rate     | in/day | Reported |                    | 0.168    | 1/App. Day         | Measured    |
|                      |        | Required | *****              | 1.0      | 1/App. Day         | Measured    |
| Application Rate     | in/wk. | Reported |                    | 1.176    | 1/Week             | Measured    |
|                      |        | Required | *****              | 2.0      | 1/Week             | Measured    |
| PH                   | S.U.   | Reported | 6.35               | 6.50     | 2/Month            | Grab        |
|                      |        | Required | 6.0 min            | 9.0      | 2/Month            | Grab        |
| Chlorides            | mg/l   | Reported | 355.00             | 410.00   | 2/Month            | Grab        |
|                      |        | Required | NL                 | NL       | 2/Month            | Grab        |
| TKN                  | mg/l   | Reported | 15.05              | 28.10    | 2/Month            | Grab        |
|                      |        | Required | NL                 | NL       | 2/Month            | Grab        |
| TKN                  | #/acre | Reported | 5.55               | 11.11    | 2/Month            | Calculated  |
|                      |        | Required | NL                 | NL       | 2/Month            | Calculated  |
| Nitrate-Nitrogen     | mg/l   | Reported | 1.35               | 2.50     | 2/Month            | Grab        |
|                      |        | Required | NL                 | NL       | 2/Month            | Grab        |
| Nitrate-Nitrogen     | #/acre | Reported | 0.47               | 0.93     | 2/Month            | Calculated  |
|                      |        | Required | NL                 | NL       | 2/Month            | Calculated  |
| Ammonia-Nitrogen     | mg/l   | Reported | 3.80               | 7.50     | 2/Month            | Grab        |
|                      |        | Required | NL                 | NL       | 2/Month            | Grab        |
| Ammonia-Nitrogen     | #/acre | Reported | 1.41               | 2.82     | 2/Month            | Calculated  |
|                      |        | Required | NL                 | NL       | 2/Month            | Calculated  |
| Available Phosphorus | mg/l   | Reported | 4.10               | 6.70     | 2/Month            | Grab        |
|                      |        | Required | NL                 | NL       | 2/Month            | Grab        |

*Tony Duncarra* COMPLIANCE MANAGER  
Name of Principal Exec. Officer or Authorized Agent / Title

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations. See 18 U.S.C. §1001 and 33 U.S.C. §1319. (Penalties under these statutes may include fines up to \$10,000 and or maximum imprisonment of between 6 months and 5 years.)

*[Signature]* 8/9/11  
Signature of Principal Officer or Authorized Agent / Date



ATTACHMENT C-1a  
DEPARTMENT OF ENVIRONMENTAL QUALITY  
Virginia Pollution Abatement Monitoring Report

Facility Name: East Coast Brokers and Packers, Incorporated  
Address: 15141 Finney Mason Road  
Mappsville, VA 23407

VPA Permit No.: VPA01057

Report Period: From 7 / 1 /2011 To 7 / 31 /2011

Monitoring Station: Spray Irrigation Wastewater From Storage Tank

| Parameters                     | Units        |          | Monitoring Results |              | Frequency of Analysis | Sample Type |
|--------------------------------|--------------|----------|--------------------|--------------|-----------------------|-------------|
|                                |              |          | Average            | Maximum      |                       |             |
| Available Phosphorus           | #/acre       | Reported | 1.50               | 3.00         | 2/Month               | Calculated  |
|                                |              | Required | NL                 | NL           | 2/Month               | Calculated  |
| Available Potassium            | mg/l         | Reported | 48.75              | 62.90        | 2/Month               | Grab        |
|                                |              | Required | NL                 | NL           | 2/Month               | Grab        |
| Available Potassium            | #/acre       | Reported | 17.59              | 35.19        | 2/Month               | Calculated  |
|                                |              | Required | NL                 | NL           | 2/Month               | Calculated  |
| Calcium                        | mg/l         | Reported | 34.25              | 44.80        | 2/Month               | Grab        |
|                                |              | Required | NL                 | NL           | 2/Month               | Grab        |
| Magnesium                      | mg/l         | Reported | 9.10               | 11.60        | 2/Month               | Grab        |
|                                |              | Required | NL                 | NL           | 2/Month               | Grab        |
| Electro-Conduct (EC)           | dS/m         | Reported | 1150.00            | 1210.00      | 2/Month               | Grab        |
|                                |              | Required | NL                 | NL*          | 2/Month               | Grab        |
| Dissolved Copper               | ug/l         | Reported | 875.00             | 1500.00      | 2/Month               | Grab        |
|                                |              | Required | NL                 | NL           | 2/Month               | Grab        |
| Dissolved Zinc                 | ug/l         | Reported | 385.50             | 469.00       | 2/Month               | Grab        |
|                                |              | Required | NL                 | NL           | 2/Month               | Grab        |
| PAN                            | #/acre       | Reported |                    | 4.73         | 1/Month               | Calculated  |
|                                |              | Required | NA                 | Attch C*     | 1/Month               | Calculated  |
| PAN                            | #/acre /year | Reported |                    | 26.00        | 1/Year                | Calculated  |
|                                |              | Required | NA                 | Attch C*     | 1/Year                | Calculated  |
| Sodium                         | mg/l         | Reported | 215.00             | 292.00       | 2/Month               | Grab        |
|                                |              | Required | NL                 | NL           | 2/Month               | Grab        |
| SAR                            | meq/l        | Reported | 8.25               | 10.04        | 2/Month               | Calculated  |
|                                |              | Required | NL                 | NL           | 2/Month               | Calculated  |
| Pesticide Scan (608) Freeboard | ug/l         | Reported | Attach pages       | Attach pages | 1/year                | Grab        |
|                                |              | Required | NA                 | NL           | 1/year                | Grab        |

*TONY DOUGARRA COMPLIANCE MANAGER*

Name of Principal Exec. Officer or Authorized Agent /

Title

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations. See 18 U.S.C. §1001 and 33 U.S.C. §1319. (Penalties under these statutes may include fines up to \$10,000 and or maximum imprisonment of between 6 months and 5 years.)

Signature of Principal Officer or Authorized Agent /

Date

*8/9/11*

**Land Application Site – Cull Field**  
**Soil Analytical Results**  
**(June 2014 – to be provided)**

## **APPENDIX C**

### **Agronomic Practices**

The general agronomic practices previously approved by permit (2004) for the facility wastewater spray disposal field follows.

A formal Nutrient Management Plan for the wastewater spray disposal field is being prepared by a certified nutrient management planner and will be forwarded for inclusion within the application package.

## **TURF MAINTENANCE**

Tall fescue grass is maintained on the spray field. The grass cover provides uptake of potential nutrients in the spray water, increases evapotranspiration, and thus disposal of the water. The grass also provides erosion and sediment control to keep soils onsite. The grass and grass root matt also increase the detention time of the spray water in the topsoil where natural processes can attenuate nutrients. No specific yield is anticipated from the cover crop; as such, tissue testing is not required.

Table 1 provides a summary of field maintenance.

| Activity                     | Spring<br>(April) | Summer | Fall<br>(September) | Winter |
|------------------------------|-------------------|--------|---------------------|--------|
| Soils Sampling               | X                 |        | X                   |        |
| Aeration                     | X                 |        |                     |        |
| pH Amendment                 | X                 |        | X                   |        |
| Pesticide (Weed) Application | X                 |        |                     |        |
| Cutting                      | X                 | X      | X                   |        |
| Irrigation                   |                   | X      | X                   |        |
| Fertilizing                  |                   |        | X                   |        |
| Thatching                    |                   |        | X                   |        |
| Reseeding                    |                   |        | X                   |        |

Soils are tested bi-annually (in April and September). During the April sampling event the turf is evaluated with respect to weed coverage. When coverage exceeds 25%, weed control is prescribed in keeping with best management practices. Specific product will be determined based on plant materials found to be present. Application will be in keeping with product labeling and best management practices.

Application of wastewater and amendment may require the use of heavy equipment on the field. If compaction is observed, aeration is best conducted in the spring.

The soil pH at land application site shall be adjusted upward with lime, and if necessary downward with elemental sulfur, to achieve and maintain a pH range approximating 5.8 – 6.5 S.U.

Soil amendment with gypsum (calcium sulfate) at the rate of 10 to 15 lbs. per 100 sq. ft. shall be made on the spray application site in the spring if the Exchangeable Sodium Percentage (ESP) in the soil is equal to or greater than 15.

During the September sampling event the turf is evaluated with respect to health, density and thatch.

- If turf health is found to be substandard, amendments may be prescribed according to recommendations provided by A&L Eastern Laboratories, Inc. located in Richmond, Virginia. Amendments shall be applied according to recommendations

and best management practices. To prevent brown patch, nitrogen fertilizers shall be kept to a minimum.

- If turf is found to lack sufficient density, the field is reseeded as per recommendations for reseeding of established turfs.
- Generally it is not necessary to thatch fescue turf however if the thatch matt is found to be inhibiting water penetration thatching will be prescribed followed by reseeding at the specified rate for established turfs.

During the active growing season the turf is cut on a weekly basis to maintain a turf height of 2.5 - 4". Spray application is monitored to ensure adequate coverage. Consistent coverage and the prevention of wet spots along with management of nitrogen is the primary control for brown patch.

## **SPRAY FIELD LAND APPLICATION METHODS AND EQUIPMENT**


The method for land application of waste wash water used at this facility will be a piped spray irrigation system and supplemented by a truck mounted spreader rack if necessary. Upon the completion of each packing work day, 2,500 gallons per day can be sprayed to the field (Figure 5) through a piped spray irrigated system. The field contains a 50ft buffer around it. If needed, wastewater is transferred from the storage tanks to a 3,000 gallon capacity spray truck using the same 48gpm transfer pump.

Each spray event will be applied to one of the spray field discharge lines. Each subsequent spray event will utilize the next sequential spray field discharge line such that the entire field will be covered over the span of 3 spray events. Application rates and active lines are adjusted by controller valves.


































Over application is prevented by the operator visually inspecting and walking on the spray field to verify that the field appears dry enough to receive the wastewater. If the field appears to be wet, no spraying will be performed.

The irrigation system is reliable and has not had any major issues during operation in the past. The irrigation system will require onsite storage of additional piping, valves, controllers, and equipment for repair. In the event that a repair needs to be done to the spray irrigation system, the spray truck may be utilized to land apply wastewater along the same discharge lines. Application rates will be adjusted by speed of the spray trucks. Truck mounted spreader rack systems are very reliable for spray irrigation systems in that they are simple and have few parts. In the event that a spray truck becomes in need of repair, or during wet periods when spraying cannot occur, the 46,000 gallon storage capacity is used to hold excess wastewater until it can be applied. If the transfer pump goes down, one-half of the volume of the vertical storage tanks can still gravity drain into the trucks providing at least 23,000-gallons of holding capacity. For longer duration mechanical problems with the spray truck, a backup spray truck from another spray irrigation operation will be used. Since the spray field has excess capacity, the application rate can be increased so that the truck will have sufficient time between spray events.

# Soil Map—Accomack County, Virginia



## MAP LEGEND

-  Area of Interest (AOI)
-  Soils
-  Soil Map Unit Polygons
-  Soil Map Unit Lines
-  Soil Map Unit Points
- Special Point Features**
  -  Blowout
  -  Borrow Pit
  -  Clay Spot
  -  Closed Depression
  -  Gravel Pit
  -  Gravelly Spot
  -  Landfill
  -  Lava Flow
  -  Marsh or swamp
  -  Mine or Quarry
  -  Miscellaneous Water
  -  Perennial Water
  -  Rock Outcrop
  -  Saline Spot
  -  Sandy Spot
  -  Severely Eroded Spot
  -  Sinkhole
  -  Slide or Slip
  -  Sodic Spot
- Water Features**
  -  Streams and Canals
- Transportation**
  -  Rails
  -  Interstate Highways
  -  US Routes
  -  Major Roads
  -  Local Roads
- Background**
  -  Aerial Photography
-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
- Special Line Features**

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:15,800.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>  
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Accomack County, Virginia  
Survey Area Data: Version 11, Dec 11, 2013

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jun 17, 2010—Jul 4, 2010

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.



Map Unit Legend

| Accomack County, Virginia (VA001) |   |              |                |
|-----------------------------------|---|--------------|----------------|
| Map Unit Symbol                   | Map Unit Name                                   | Acres in AOI | Percent of AOI |
| BhB                               | Bojac loamy sand, 2 to 6 percent slopes         | 0.0          | 0.0%           |
| BkA                               | Bojac sandy loam, 0 to 2 percent slopes         | 1.6          | 38.5%          |
| DrA                               | Dragston fine sandy loam, 0 to 2 percent slopes | 0.1          | 2.8%           |
| MuA                               | Munden sandy loam, 0 to 2 percent slopes        | 2.4          | 58.7%          |
| Totals for Area of Interest       |   | 4.1          | 100.0%         |

The general agronomic practices previously approved by permit (2004) for the facility cull disposal field follows.

A formal Nutrient Management Plan for the wastewater spray disposal field is being prepared by a certified nutrient management planner and will be forwarded for inclusion within the application package.

## **CULL DISPOSAL**


Culls are defined as product that is not fit for wholesale distribution. Product is determined to be a cull when its size falls outside of certain criteria (either too large or too small, is physically defective (malformed or ruptured) or is over ripe for packaging.

Culls are separated from marketable product after the wash process which effectively removes or reduces trace pesticides. Culls are conveyed by a spreader truck to a section of the “cull field” identified on Figure 5. Total acreage is 17.1 acres inclusive of 50 foot buffer strips that are maintained around the perimeter of each field. Sections of the field use are rotated as they become full.

A mechanical spreader ruptures the fruit to facilitate dehydration and decomposition once applied. Typically the partially dehydrated and decomposed fruits are further worked into the receiving soils via mechanical disc in the soils within 48 hours of applications.

Cull application is generally conducted from July – October. Off season, the fields are planted with either rye or oat grasses to provide both stabilization and nutrient uptake. In 2011 a total of 2,048 tons of culls were incorporated into the cull fields this was a low average application year.
























































































































# Soil Map—Accomack County, Virginia



Map Scale: 1:2,570 if printed on A landscape (11" x 8.5") sheet.

Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 18N WGS84

## MAP LEGEND

|   |                        |   |                        |   |                      |   |                        |   |                        |   |                     |   |                     |   |                |   |                     |   |                     |   |                    |   |                    |   |                    |   |                    |   |                    |
|---|------------------------|---|------------------------|---|----------------------|---|------------------------|---|------------------------|---|---------------------|---|---------------------|---|----------------|---|---------------------|---|---------------------|---|--------------------|---|--------------------|---|--------------------|---|--------------------|---|--------------------|
|    | Area of Interest (AOI) |    | Soil Map Unit Polygons |    | Soil Map Unit Lines  |    | Soil Map Unit Points   |    | Special Point Features |    | Water Features      |    | Streams and Canals  |    | Transportation |    | Rails               |    | Interstate Highways |    | US Routes          |    | Major Roads        |    | Local Roads        |    | Background         |    | Aerial Photography |
|    | Soils                  |    | Soil Map Unit Polygons |    | Soil Map Unit Lines  |    | Soil Map Unit Points   |    | Special Point Features |    | Water Features      |    | Streams and Canals  |    | Transportation |    | Rails               |    | Interstate Highways |    | US Routes          |    | Major Roads        |    | Local Roads        |    | Background         |    | Aerial Photography |
|    | Soil Map Unit Polygons |    | Soil Map Unit Polygons |    | Soil Map Unit Lines  |    | Soil Map Unit Points   |    | Special Point Features |    | Water Features      |    | Streams and Canals  |    | Transportation |    | Rails               |    | Interstate Highways |    | US Routes          |    | Major Roads        |    | Local Roads        |    | Background         |    | Aerial Photography |
|    | Soil Map Unit Lines    |    | Soil Map Unit Lines    |    | Soil Map Unit Points |    | Special Point Features |    | Water Features         |    | Streams and Canals  |    | Transportation      |    | Rails          |    | Interstate Highways |    | US Routes           |    | Major Roads        |    | Local Roads        |    | Background         |    | Aerial Photography |   |                    |
|    | Soil Map Unit Points   |    | Special Point Features |    | Water Features       |    | Streams and Canals     |    | Transportation         |    | Rails               |    | Interstate Highways |    | US Routes      |    | Major Roads         |    | Local Roads         |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |   |                    |
|    | Special Point Features |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|    | Blowout                |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|    | Borrow Pit             |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|    | Clay Spot              |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|    | Closed Depression      |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|    | Gravel Pit             |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|    | Gravelly Spot          |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|    | Landfill               |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|    | Lava Flow              |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|    | Marsh or swamp         |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|    | Mine or Quarry         |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|    | Miscellaneous Water    |    | Water Features         |    | Streams and Canals   |    | Transportation         |    | Rails                  |    | Interstate Highways |    | US Routes           |    | Major Roads    |    | Local Roads         |    | Background          |    | Aerial Photography |    | Background         |    | Aerial Photography |    | Background         |    | Aerial Photography |
|   | Perennial Water        |   | Water Features         |   | Streams and Canals   |   | Transportation         |   | Rails                  |   | Interstate Highways |   | US Routes           |   | Major Roads    |   | Local Roads         |   | Background          |   | Aerial Photography |   | Background         |   | Aerial Photography |   | Background         |   | Aerial Photography |
|  | Rock Outcrop           |  | Water Features         |  | Streams and Canals   |  | Transportation         |  | Rails                  |  | Interstate Highways |  | US Routes           |  | Major Roads    |  | Local Roads         |  | Background          |  | Aerial Photography |  | Background         |  | Aerial Photography |  | Background         |  | Aerial Photography |
|  | Saline Spot            |  | Water Features         |  | Streams and Canals   |  | Transportation         |  | Rails                  |  | Interstate Highways |  | US Routes           |  | Major Roads    |  | Local Roads         |  | Background          |  | Aerial Photography |  | Background         |  | Aerial Photography |   |                    |   |                    |
|  | Sandy Spot             |  | Water Features         |  | Streams and Canals   |  | Transportation         |  | Rails                  |  | Interstate Highways |  | US Routes           |  | Major Roads    |  | Local Roads         |  | Background          |  | Aerial Photography |  | Background         |  | Aerial Photography |   |                    |   |                    |
|  | Severely Eroded Spot   |  | Water Features         |  | Streams and Canals   |  | Transportation         |  | Rails                  |  | Interstate Highways |  | US Routes           |  | Major Roads    |  | Local Roads         |  | Background          |  | Aerial Photography |  | Background         |  | Aerial Photography |   |                    |   |                    |
|  | Sinkhole               |  | Water Features         |  | Streams and Canals   |  | Transportation         |  | Rails                  |  | Interstate Highways |  | US Routes           |  | Major Roads    |  | Local Roads         |  | Background          |  | Aerial Photography |  | Background         |  | Aerial Photography |   |                    |   |                    |
|  | Slide or Slip          |  | Water Features         |  | Streams and Canals   |  | Transportation         |  | Rails                  |  | Interstate Highways |  | US Routes           |  | Major Roads    |   |                     |   |                     |   |                    |   |                    |   |                    |   |                    |   |                    |

## Map Unit Legend

| Accomack County, Virginia (VA001) |   |              |                |
|-----------------------------------|---|--------------|----------------|
| Map Unit Symbol                   | Map Unit Name                                   | Acres in AOI | Percent of AOI |
| BhB                               | Bojac loamy sand, 2 to 6 percent slopes         | 4.9          | 28.6%          |
| BkA                               | Bojac sandy loam, 0 to 2 percent slopes         | 0.1          | 0.7%           |
| DrA                               | Dregston fine sandy loam, 0 to 2 percent slopes | 5.4          | 31.9%          |
| NmA                               | Nimmo sandy loam, 0 to 2 percent slopes         | 6.6          | 38.9%          |
| Totals for Area of Interest       |   | 17.1         | 100.0%         |



|                                     |     |
|-------------------------------------|-----|
| Depth to Perched Water:             | n/e |
| Depth to Seasonal High Water Table: | ~5  |
| Depth to Current Water Table:       | n/e |
| Depth to Seasonal Low Water Table:  | n/e |

[illegible]



**BORING NO:**

# BhB

**PROJECT NO:** 99167A

DATE: 1/20/2004

**Depth to Seasonal High Water Table: ~6**

**Depth to Seasonal Low Water Table:** n/e

**Depth to Seasonal Low Water Table:** n/e

[illegible]



## **APPENDIX D**

### Calculations

Spray field calculations to be included with the new Nutrient Management Plan

Calculations are based on the following parameters:

- The subject spray field is 4.1 acres.
- Bojac soil series – slope 0-2% (BkA)
- Munden soil series – slope 0-2% (MuA)
- The “crop” is a year round permanent stand of tall fescue.

# Potential Evapotranspiration Calculations



| Month | Air Temp<br>(Avg °C/Day) | Sunshine Factor<br>[b] | Heat Index<br>[i] | P.E.T.<br>(cm) | P.E.T.<br>(in) |
|-------|--------------------------|------------------------|-------------------|----------------|----------------|
| JAN   | 2                        | 0.86                   | 0.25              | 0.15           | 0.06           |
| FEB   | 4                        | 0.84                   | 0.71              | 0.52           | 0.20           |
| MAR   | 10                       | 1.03                   | 2.85              | 2.65           | 1.04           |
| APR   | 13                       | 1.10                   | 4.23              | 4.51           | 1.78           |
| MAY   | 16                       | 1.22                   | 5.79              | 6.90           | 2.72           |
| JUN   | 23                       | 1.23                   | 10.02             | 13.09          | 5.15           |
| JUL   | 24                       | 1.25                   | 10.95             | 13.85          | 5.45           |
| AUG   | 25                       | 1.17                   | 11.71             | 13.94          | 5.49           |
| SEP   | 22                       | 1.04                   | 5.52              | 10.26          | 4.04           |
| OCT   | 22                       | 0.97                   | 9.37              | 9.27           | 3.65           |
| NOV   | 14                       | 0.85                   | 4.73              | 3.94           | 1.55           |
| DEC   | 12                       | 0.83                   | 3.75              | 2.88           | 1.13           |

Annual Potential Evapotranspiration = 81.96 32.27

$$PET = 1.62b [10T/i]^a$$

b = sunshine factor [mean possible hours of bright sunlight(30days/12hours)]

T = mean monthly air temperature (°C)

i = Heat Index

a = empirical coefficient

Air Temp = Average daily temperature at Painter, Virginia 1955-2012

Thornthwaite, 1948

## HYDRAULIC LOADING CALCULATIONS

|   | Jul-2011 | Aug-2011 | Sep-2011 | Average       |
|---|----------|----------|----------|---------------|
| <b>1. Monthly Precipitation (in)</b>  | 5.0      | 4.3      | 4.0      | <b>4.43</b>   |
| Daily precipitation (in)  | 0.161    | 0.139    | 0.133    | <b>0.14</b>   |
| <b>2. Monthly Evapotranspiration (in)</b>   | 5.45     | 5.49     | 4.04     | <b>4.99</b>   |
| Daily PET (in)  | 0.176    | 0.177    | 0.135    | <b>0.16</b>   |
| <b>3. Soil Percolation Rate* (mpi)</b>  |          |          |          | <b>30</b>     |
| Potential daily infiltration (in/4-hr day)  |          |          |          | <b>8.00</b>   |
| <i>Does infiltration capacity exceed permitted application rate (1"/day)? (Y/N)</i> |          |          |          | <b>Y</b>      |
| <b>4. Monthly Wastewater Loading (MG)**</b>   | 0.468    | 0.468    | 0.480    | <b>0.472</b>  |
| Average daily wastewater loading (MG)   | 0.0151   | 0.0151   | 0.0160   | <b>0.0154</b> |
| <b>5. Storage Requirement (MG/3-days)</b>   | 0.045    | 0.045    | 0.048    | <b>0.046</b>  |
| Storage provided (MG)   |          |          |          | <b>0.046</b>  |
| <i>Does loading rate exceed storage demand? (Y/N)</i>                               |          |          |          | <b>N</b>      |
| <b>Land Area Requirement</b>  |          |          |          |               |
| Average loading per month (MG)  | 0.468    | 0.468    | 0.480    | <b>0.472</b>  |
| Maximum spray depth allowed per month (in)  | 8        | 8        | 8        | <b>8</b>      |
| Minimum acres required  | 2.16     | 2.16     | 2.21     | <b>2.17</b>   |
| Acres provided  |          | 4.1      |          | <b>4.1</b>    |
| <i>Does provided spray field area meet requirements? (Y/N)</i>                      |          |          |          | <b>Y</b>      |
| <b>6. Monthly Storage Input/Drawdown</b>  |          |          |          |               |
| Storage Input [loading] (MG)  | 0.468    | 0.468    | 0.480    | 0.472         |
| Potential Drawdown [spraying] (MG)  | 0.891    | 0.891    | 0.891    | 0.891         |
| Monthly Input/Drawdown Ratio  | 0.53     | 0.53     | 0.54     | 0.530         |
| <i>Is monthly input/drawdown ratio &lt; 1? (Y/N)</i>                                |          |          |          | <b>Y</b>      |

\* Infiltration rate estimate based on soil texture.

\*\* From 2011 DMR

## EVAPOTRANSPIRATION

The combined water losses from evaporation and vegetative transpiration are termed evapotranspiration (ET). Evaporation is relatively easy to measure using evaporative pan data, however transpiration is difficult to quantify without direct field measurements. Actual ET losses from a site are most readily estimated through calculation. The thickness (relative depth) of soil water loss through ET can, however, be empirically determined.

When this thickness is multiplied by an area, a volume of water loss may be calculated.

Thornthwaith (1948) developed a relationship for monthly potential evapotranspiration (PET) based on an a heat index and empirical coefficients for available sunshine and crop transpiration. Braas (1990) simplified the equation to:

$$PET = 1.62b \times [10T/I]^a$$

where,  $b$  is an adjustment factor for daily available sunshine,  $T$  is the mean monthly temperature ( $^{\circ}\text{C}$ ),  $I$  is the annual heat index, and  $a$  is a relative parameter based on  $I$ .

The Thornthwaite approach assumes that the soil water available for ET is not limited. Therefore, this calculation yields potential evapotranspiration (PET) which is an estimation of a maximum thickness of soil water loss.


Results of the PET calculations estimate the monthly relative thickness of water loss. These monthly thicknesses were multiplied by the area of the YYYYYY (Z.ZZ ac,ft.) and the resultant volumes added together to calculate the approximate annual volume of its' evapotranspirative losses. The total estimated annual volume of water loss through PET at YYYYYYY YYYYYYY is ZZ.ZZ gal/ft'. A data listing and monthly breakdown of PET quantities is provided  
\*\*\*\*\*.

Braas, R.L., 1990. Hydrology: an introduction to hydrologic science. New York: Addison-Wesley Publishing Company.  
pp 224-225.

Thornthwaite, C.W., 1948. An approach toward a rational classification of climate. *Am. Geogr. Rev.* 38:55-94

## **APPENDIX E**

### **Additional Notes**

**MSA, P.C.**5033 Rouse Drive, Virginia Beach, VA 23462-3708 • (757) 490-9264 • (757) 490-0634 [fax] • [www.msaonline.com](http://www.msaonline.com)

Offices in Hampton Roads and Virginia's Eastern Shore

Environmental Sciences • Planning • Surveying • Civil &amp; Environmental Engineering • Landscape Architecture

**A REQUEST FOR MONITORING WAIVER**

A waiver is requested for monitoring requirements identified in the Virginia Pollution Abatement renewal application of the subject permitted facility.

The facility is a tomato washing operation where chlorinated groundwater is used to facilitate the washing and packaging of agricultural products. In this case tomatoes are the sole product processed. The VPA permit covers the land disposal of spent wash water and tomato culls.

Given the nature of the spray operation, waivers for several of the monitoring parameters listed on the permit application are requested. Waiver requests for parameters listed on Form C section 4.a. of the application, along with justifications for the effluent stream are listed in Table I.

**Table I Effluent Stream Monitoring**

| <b>Parameter</b>   | <b>Wavier Rational</b>   |
|--------------------|--|
| BOD mg/L           | Generally associated with high concentrations of nitrogen where biological activity would create a high O2 demand. Is of a particular concern if being discharged to surface waters. The effluent stream does not have high levels of nutrients and in not surface water applied.                                  |
| COD mg/L           | Oxygen demand of organic and inorganic substances as measured by indicator chemicals. Water is too free from organic substances to expect elevated COD. Is of a particular concern if being discharged to surface waters. The effluent stream is not industrial in nature and is not discharged to surface waters. |
| TOC mg/L           | The amount of organic carbon in the effluent stream is not reasonably expected to be at a level that would negatively impact non-aquatic environments.   |
| TSS mg/L           | Solids in the effluent stream are not apparent and settled out in the storage tanks. Given the nature of the spray operations any solids present are not expected to reach and impact surface waters.  |
| Percent Solids (%) | Not anticipated to be a factor. Solids will settle out in holding tanks.   |

**Table II Soil Monitoring**

| <b>Parameter</b>                                     | <b>Wavier Rational</b>  |
|--|---|
| Soil Organic Matter (%)                              | Relative to crop requirements, the effluent stream is deficient in N, which allows for a healthful accumulation of organic material.  |
| Organic Nitrogen (ppm)                               | Total nitrogen is inclusive. Wash water rinses fruit and does not pick up organic material that might elevate organic nitrogen. Potential concentration is expected to be very low. |
| Ammonia Nitrogen (ppm)                               | Not anticipated in effluent stream  |
| Available Phosphorus (ppm)                           | Not anticipated in effluent stream  |
| Exchangeable Magnesium (mg/100g)                     | Not anticipated in effluent stream  |
| Copper (ppm)   | Calculated loading provides a better estimate of accumulation   |
| Nickel (ppm)   | Not anticipated in effluent stream  |
| Zinc (ppm)   | Calculated loading provides a better estimate of accumulation   |
| Cadmium (ppm)  | Not anticipated in effluent stream  |
| Lead (ppm)   | Not anticipated in effluent stream  |
| Chromium (ppm)                                       | Not anticipated in effluent stream  |
| Manganese (ppm)                                      | Not anticipated in effluent stream  |
| Particle Size Analysis or USDA Textural Estimate (%) | Soil type and composition was determined during initial application. Soils well characterized.  |

## **APPENDIX F**

### References



**BkA—Bojac sandy loam, 0 to 2 percent slopes**

**Setting**

*Landform:* Stream terraces

*Landscape position:* Nearly level and undulating surfaces

*Size of areas:* 5 to 1,200 acres

**Composition**

Bojac and similar soils: 85 to 95 percent

Dissimilar inclusions: 5 to 15 percent

**Inclusions**

*Dissimilar Inclusions:*

- Dragston soils, which have a grayer subsoil than the Bojac soil; on the rims of depressions, on flats, and in depressions.

*Similar soils:*

- Soils that have about 2 to 15 percent gravel in the subsoil and about 5 to 50 percent gravel in the substratum; in landscape positions similar to those of the Bojac soil

**Typical Profile**

0 to 7 inches—brown sandy loam

7 to 27 inches—strong brown loam

27 to 33 inches—strong brown sandy loam

33 to 40 inches—strong brown loamy sand

40 to 85 inches—pale brown sand

**Soil Properties and Qualities**

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Low

*Organic matter content:* Low

*Soil reaction:* Extremely acid to slightly acid in the surface layer and subsoil, very strongly acid to moderately acid in the substratum

*Natural fertility:* Low

*Surface runoff:* Slow

*Hazard of water erosion:* Low

*Hazard of wind erosion:* Medium

*Depth to water table:* 48 to 72 inches

*Root zone:* More than 60 inches

*Shrink-swell potential:* Low

*Corrosivity:* To concrete—high; to steel—low

**Use and Management**

**Cropland**

*Suitability for cultivated crops:* Well suited

*Suitability for nursery crops:* Well suited (fig. 7)

*Management concerns:*

- Droughtiness, which can be overcome by applying irrigation water
- The hazard of wind erosion, which can be reduced by establishing windbreaks, leaving plant residue on the surface, and using a conservation tillage system

- Low content of organic matter, which can be increased by incorporating plant residue into the soil

**Pasture**

*Suitability for grasses and legumes:* Well suited

*Management concerns:*

- Droughtiness, which can be overcome by applying irrigation water

**Woodland**

*Potential productivity for loblolly pine:* High

*Site index for loblolly pine:* 80

*Estimated annual production of loblolly pine:* 115 cubic feet per acre

*Management concerns:*

- No major concerns

**Septic tank absorption fields**

*Suitability:* Well suited

- Seasonal wetness, which can be reduced by placing the absorption field above the high water table

**Building sites**

*Suitability:* Well suited

*Management concerns:*

- Sloughing, which can be prevented by shoring excavation walls
- Wetness, which can be reduced by installing a drainage system
- Droughtiness, which can be overcome by applying irrigation water

**Recreational areas**

*Suitability:* Well suited

*Management concerns:*

- No major concerns

**Interpretive Groups**

*Land capability classification:* IIs

*Woodland ordination symbol:* 8A

## **Bojac Series**

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Parent material:* Unconsolidated sediments

*Slope range:* 0 to 6 percent

### **Typical Pedon**

Bojac sandy loam, 0 to 2 percent slopes, about 1.3 miles south-southeast of the junction of U.S. Highway 13 (business route) and Virginia Highway 605 and 1.5 miles south-southwest of the junction of U.S. Highway 13 (business route) and Virginia Highway 652, near Accomac:

- Ap—0 to 7 inches; brown (10YR 4/3) sandy loam; weak medium granular structure; friable, slightly sticky and slightly plastic; few fine roots; strongly acid; abrupt smooth boundary.
- Bt1—7 to 27 inches; strong brown (7.5YR 5/6) loam; weak medium subangular blocky structure; friable, slightly sticky and slightly plastic; few fine roots; many distinct clay bridges between sand grains; few faint clay films in pores; very strongly acid; gradual smooth boundary.
- Bt2—27 to 33 inches; strong brown (7.5YR 5/6) sandy loam; weak medium subangular blocky structure; friable, slightly sticky and slightly plastic; many distinct clay bridges between sand grains; few faint clay films in pores; strongly acid; gradual smooth boundary.
- Bt3—33 to 40 inches; strong brown (7.5YR 5/8) loamy sand; weak coarse subangular blocky structure; very friable; many distinct clay bridges between sand grains; strongly acid; gradual smooth boundary.
- C—40 to 85 inches; pale brown (10YR 6/3) sand; single grain; loose; strongly acid.

### **Range in Characteristics**

*Thickness of the solum:* 30 to 65 inches

*Soil reaction:* Extremely acid to slightly acid in the A, E, and Bt horizons, very strongly acid to moderately acid in the C horizon

*Content of coarse fragments:* 0 to 5 percent in the solum and 0 to 15 percent in the C horizon

*A horizon (not in all pedons):*

Hue—7.5YR to 2.5Y

Value—3 or 4

Chroma—1 to 3

Texture—loamy sand, loamy fine sand, sandy loam, fine sandy loam, or loam

*Ap horizon:*

Hue—7.5YR to 2.5Y

Value—4 to 6

Chroma—1 to 4

Texture—loamy sand, loamy fine sand, sandy loam, fine sandy loam, or loam

*E horizon (not in all pedons):*

Hue—10YR or 2.5Y

Value—4 to 7

Chroma—4 to 6

Texture—loamy sand, loamy fine sand, sandy loam, fine sandy loam, or loam

*Bt horizon:*

Hue—7.5YR or 10YR

Value—4 to 6

Chroma—4 to 8

Texture—sandy loam, fine sandy loam, or loam

Other features—a thin subhorizon of sandy clay loam or clay loam in some pedons, a lower subhorizon of loamy sand or loamy fine sand in other pedons

*C horizon:*

Hue—7.5YR to 2.5Y

Value—4 to 7

Chroma—3 to 8

Other features—high-chroma mottles, low-chroma mottles, or both in many pedons

Texture—stratified coarse sand, sand, fine sand, loamy coarse sand, loamy sand, or loamy fine sand

**DrA—Dragston fine sandy loam, 0 to 2 percent slopes**

**Settling**

*Landform:* Stream terraces

*Landscape position:* Rims of depressions, flats, and depressions

*Size of areas:* 5 to 150 acres

**Composition**

Dragston and similar soils: 85 to 95 percent

Dissimilar inclusions: 5 to 15 percent

**Inclusions**

*Dissimilar Inclusions:*

- Arapahoe soils, which have a darker surface layer than the Dragston soil; on flats and in depressions
- Seabrook soils, which have a less developed subsoil than the Dragston soil; in nearly level, slightly elevated areas

*Similar soils:*

- Munden soils, which have a browner subsoil than the Dragston soil; in nearly level, slightly elevated areas
- Soils that have about 2 to 15 percent gravel in the subsoil and about 5 to 50 percent gravel in the substratum; in landscape positions similar to those of the Dragston soil

**Typical Profile**

0 to 6 inches—dark grayish brown fine sandy loam

6 to 15 inches—light olive brown loam that has light brownish gray and strong brown mottles

15 to 30 inches—gray loam that has yellowish red mottles

30 to 40 inches—gray fine sandy loam that has yellowish red mottles

40 to 85 inches—light gray fine sand that has yellowish red and brownish yellow mottles

**Soil Properties and Qualities**

*Drainage class:* Somewhat poorly drained

*Permeability:* Moderately rapid in the subsoil and rapid in the substratum

*Available water capacity:* Moderate

*Organic matter content:* Low

*Soil reaction:* Very strongly acid or strongly acid in the surface layer and the upper part of the subsoil, very strongly acid to slightly acid in the lower part of the subsoil and in the substratum

*Surface runoff:* Slow

*Hazard of water erosion:* Low

*Hazard of wind erosion:* Medium

*Depth to water table:* 12 to 30 inches

*Root zone:* More than 60 inches

*Shrink-swell potential:* Low

*Corrosivity:* To concrete—high; to steel—low

**Use and Management**

**Cropland**

*Suitability for cultivated crops:* Moderate

*Suitability for nursery crops:* Moderate

*Management concerns:*

- Wetness, which can be reduced by installing a drainage system
- Low content of organic matter, which can be increased by incorporating plant residue into the soil
- The hazard of wind erosion in drained areas, which can be reduced by establishing windbreaks, leaving plant residue on the surface, and using a conservation tillage system

**Pasture**

*Suitability for grasses and legumes:* Moderate

*Management concerns:*

- Wetness, which can be reduced by installing a drainage system

**Woodland**

*Potential productivity for loblolly pine:* Very high

*Site index for loblolly pine:* 86

*Estimated annual production of loblolly pine:* 123 cubic feet per acre

*Management concerns:*

- Wetness

**Septic tank absorption fields**

*Suitability:* Poor

*Management concerns:*

- Wetness, which can be reduced by providing a drainage system and placing the absorption field above the level of the seasonal high water table
- Poor filtering capacity, which can be overcome by increasing the size of the field

**Building sites**

*Suitability:* Poor

*Management concerns:*

- Wetness, which can be reduced by installing a drainage system
- Sloughing, which can be prevented by shoring excavation walls
- Droughtiness, which can be overcome by applying irrigation water

**Recreational areas**

*Suitability:* Poor

*Management concerns:*

- Wetness

**Interpretive Groups**

*Land capability classification:* IVw

*Woodland ordination symbol:* 9W

## ***Dragston Series***

*Depth class:* Very deep

*Drainage class:* Somewhat poorly drained

*Permeability:* Moderately rapid in the subsoil, rapid in the substratum

*Parent material:* Unconsolidated sediments

*Slope range:* 0 to 2 percent

### **Typical Pedon**

Dragston fine sandy loam, 0 to 2 percent slopes, about 0.7 mile south-southwest of the junction of Virginia Highways 693 and 793 and 1.2 miles north-northeast of the junction of Virginia Highways 692 and 693, near Hallwood:

Ap—0 to 6 inches; dark grayish brown (10YR 4/2) fine sandy loam; weak medium granular structure; friable, slightly sticky and slightly plastic; common fine roots; very strongly acid; clear smooth boundary.

Bt—6 to 15 inches; light olive brown (2.5Y 5/6) loam; many medium distinct light brownish gray (10YR 6/2) and strong brown (7.5YR 5/6) mottles; weak medium subangular blocky structure; friable, slightly sticky and slightly plastic; few fine roots; many distinct clay bridges between sand grains; few faint clay films in pores; very strongly acid; gradual smooth boundary.

Btg1—15 to 30 inches; gray (10YR 6/1) loam; many medium distinct yellowish red (5YR 5/6) mottles; weak medium subangular blocky structure; friable, slightly sticky and slightly plastic; few fine roots; many distinct clay bridges between sand grains; few faint clay films in pores; very strongly acid; gradual smooth boundary.

Btg2—30 to 40 inches; gray (10YR 6/1) fine sandy loam; many medium distinct yellowish red (5YR 5/6) mottles; weak medium subangular blocky structure; friable, slightly sticky and slightly plastic; few fine roots; many distinct clay bridges between sand grains; few faint clay films in pores; very strongly acid; gradual smooth boundary.

Cg—40 to 85 inches; light gray (10YR 7/2) fine sand; many medium distinct yellowish red (5YR 5/6) and brownish yellow (10YR 6/6) mottles; single grain; loose; very strongly acid.

### **Range in Characteristics**

*Thickness of the solum:* 25 to 50 inches

*Soil reaction:* Very strongly acid or strongly acid in the Ap and Bt horizons, very strongly acid to slightly acid in the Btg and Cg horizons

*Content of coarse fragments:* 0 to 2 percent in the solum, 0 to 10 percent in the Cg horizon

*A horizon (not in all pedons):*

Hue—10YR to 5Y

Value—2 to 5

Chroma—1 to 4

Texture—loamy sand, loamy fine sand, sandy loam, fine sandy loam, or loam

*Ap horizon:*

Hue—10YR to 5Y

Value—2 to 5

Chroma—1 to 4

Texture—loamy sand, loamy fine sand, sandy loam, fine sandy loam, or loam

*Bt horizon:*

Hue—10YR to 5Y

Value—4 to 6

Chroma—3 to 8

Other features—high- and low-chroma mottles

Texture—sandy loam, fine sandy loam, or loam

*Btg horizon:*

Hue—10YR to 5Y or neutral

Value—4 to 6

Chroma—0 to 2

Other features—high- and low-chroma mottles

Texture—sandy loam, fine sandy loam, or loam

*Cg horizon:*

Hue—10YR to 5BG or neutral

Value—4 to 7

Chroma—0 to 2

Other features—high- and low-chroma mottles

Texture—sand, fine sand, loamy sand, or loamy fine sand

**MuA—Munden sandy loam, 0 to 2 percent slopes**

***Setting***

*Landform:* Coastal-plain uplands and stream terraces  
*Landscape position:* Nearly level surfaces  
*Size of areas:* 5 to 300 acres

***Composition***

Munden and similar soils: 85 to 95 percent  
Dissimilar inclusions: 5 to 15 percent

***Inclusions***

***Dissimilar inclusions:***

- Nimmo soils, which have a grayer subsoil than the Munden soil; on flats and in depressions

***Similar soils:***

- Seabrook soils, which have a sandier subsoil than the Munden soil; in landscape positions similar to those of the Munden soil
- Soils that have about 5 to 35 percent gravel in the subsoil and substratum; in landscape positions similar to those of the Munden soil

***Typical Profile***

0 to 8 inches—dark grayish brown sandy loam  
8 to 20 inches—yellowish brown loam  
20 to 25 inches—yellowish brown sandy loam that has reddish yellow and pale brown mottles  
25 to 40 inches—yellowish brown sandy loam that has reddish yellow and light gray mottles  
40 to 55 inches—mottled pale brown and grayish brown loamy sand  
55 to 85 inches—grayish brown fine sand

***Soil Properties and Qualities***

*Drainage class:* Moderately well drained  
*Permeability:* Moderately rapid in the subsoil, moderately rapid or rapid in the substratum  
*Available water capacity:* Low  
*Organic matter content:* Low  
*Soil reaction:* Very strongly acid to moderately acid  
*Natural fertility:* Low  
*Surface runoff:* Slow  
*Hazard of water erosion:* Low  
*Hazard of wind erosion:* High  
*Depth to water table:* 18 to 30 inches  
*Root zone:* More than 60 inches  
*Shrink-swell potential:* Low  
*Corrosivity:* To concrete—high; to steel—low

***Use and Management***

***Cropland***

*Suitability for cultivated crops:* Well suited  
*Suitability for nursery crops:* Well suited (fig. 12)  
*Management concerns:*  
• Wetness early in the growing season, which can be reduced by installing a drainage system

- Droughtiness later in the growing season, which can be overcome by applying irrigation water
- Low content of organic matter, which can be increased by incorporating plant residue into the soil

***Pasture***

*Suitability for grasses and legumes:* Well suited  
*Management concerns:*

- Wetness

***Woodland***

*Potential productivity for loblolly pine:* Very high  
*Site index for loblolly pine:* 90  
*Estimated annual production of loblolly pine:* 130 cubic feet per acre

*Management concerns:*

- Wetness

***Septic tank absorption fields***

*Suitability:* Moderate

*Management concerns:*

- Wetness, which can be reduced by placing the absorption field above the level of the seasonal high water table
- Poor filtering capacity, which can be overcome by increasing the size of the field

***Building sites***

*Suitability:* Well suited

*Management concerns:*

- Sloughing, which can be prevented by shoring excavation walls
- Wetness, which can be reduced by installing a drainage system
- Droughtiness, which can be overcome by applying irrigation water

***Recreational areas***

*Suitability:* Well suited

*Management concerns:*

- Wetness, droughtiness

***Interpretive Groups***

*Land capability classification:* 11w

*Woodland ordination symbol:* 9W

## **Munden Series**

*Depth class:* Very deep

*Drainage class:* Moderately well drained

*Permeability:* Moderately rapid in the subsoil,  
moderately rapid or rapid in the substratum

*Parent material:* Unconsolidated sediments

*Slope range:* 0 to 2 percent

### **Typical Pedon**

Munden sandy loam, 0 to 2 percent slopes, 0.8 mile south-southeast of the junction of Virginia Highways 658 and 682 and 1.2 miles west-southwest of the junction of Virginia Highways 681 and 316, near Bloxom:

Ap—0 to 8 inches; dark grayish brown (10YR 4/2) sandy loam; weak medium granular structure; friable, slightly sticky and slightly plastic; common fine and medium roots; very strongly acid; clear smooth boundary.

Bt1—8 to 20 inches; yellowish brown (10YR 5/6) loam; common medium distinct reddish yellow (7.5YR 6/8) mottles; weak medium subangular blocky structure; friable, sticky and slightly plastic; common fine and medium roots; many distinct clay bridges between sand grains; few faint clay films in pores; very strongly acid; gradual smooth boundary.

Bt2—20 to 25 inches; yellowish brown (10YR 5/6) sandy loam; common medium distinct reddish yellow (7.5YR 6/8) and pale brown (10YR 6/3) mottles; weak medium subangular blocky structure; friable, sticky and slightly plastic; few fine roots; many distinct clay bridges between sand grains; few faint clay films in pores; very strongly acid; gradual smooth boundary.

Bt3—25 to 40 inches; yellowish brown (10YR 5/6) sandy loam; many medium distinct reddish yellow (7.5YR 6/8) and light gray (10YR 7/2) mottles; weak medium subangular blocky structure; friable, slightly sticky and slightly plastic; many distinct clay bridges between sand grains; few faint clay films in pores; very strongly acid; gradual smooth boundary.

C—40 to 55 inches; mottled pale brown (10YR 6/3) and grayish brown (10YR 5/2) loamy sand; single grain; loose; strongly acid; gradual smooth boundary.

Cg—55 to 85 inches; grayish brown (10YR 5/2) fine sand; single grain; loose; strongly acid.

### **Range in Characteristics**

*Thickness of the solum:* 25 to 45 inches

*Soil reaction:* Very strongly acid to moderately acid

*Content of coarse fragments:* 0 to 5 percent

*Ap horizon:*

Hue—10YR or 2.5Y

Value—3 to 5

Chroma—1 to 4

Texture—loamy sand, loamy fine sand, sandy loam, fine sandy loam, or loam

*Upper part of the Bt horizon:*

Hue—7.5YR to 2.5Y

Value—3 to 6

Chroma—4 to 8

Texture—sandy loam, fine sandy loam, or loam

*Lower part of the Bt horizon:*

Hue—7.5YR to 2.5Y

Value—3 to 6

Chroma—3 to 8

Texture—sandy loam, fine sandy loam, or loam

*Btg horizon (not in all pedons):*

Hue—7.5YR to 2.5Y or neutral

Value—3 to 6

Chroma—0 to 2

Texture—sandy loam, fine sandy loam, or loam;  
subhorizons of sandy clay loam

*C horizon:*

Hue—7.5YR to 5Y

Value—5 to 7

Chroma—3 to 8

Other features—mottles that have chroma of 0 to 8  
Texture—sand, fine sand, loamy sand, loamy fine sand, sandy loam, or fine sandy loam

*Cg horizon:*

Hue—7.5YR to 5Y or neutral

Value—5 to 7

Chroma—0 to 2

Texture—sand, fine sand, loamy sand, loamy fine sand, sandy loam, or fine sandy loam

**AUTHORIZATION TO BILL APPLICANT FOR  
A PUBLIC NOTICE  
FOR  
DEL MONTE FRESH PRODUCTION INC PROCESSING PLANT,  
MAPPSVILLE VA  
RE: PERMIT NO. VPA01057**

I hereby authorize the Department of Environmental Quality to have the cost of publishing a public notice billed to the Agent/Department shown below. The public notice will be published once a week for two consecutive weeks in the: **EASTERN SHORE NEWS**

Agent/Department to be billed: Albert Garcia, General Manager of Tomato Operations

Del Monte Fresh Production, Inc

Applicant's Address:

5050 State Route 60W, Mulberry, FL  
33860

Agent's Telephone No:

863-844-5845

**I AM ALSO AUTHORIZING THE EASTERN SHORE NEWS TO SEND THE AFFIDAVIT TO:**

**DEQ TIDEWATER REGIONAL OFFICE  
ATTN: WATER PERMITS  
5636 SOUTHERN BOULEVARD  
VIRGINIA BEACH, VA 23462**

Authorizing Agent/Date Signed:

PAUL J. Rice 6/3/14  
Print Name/Date Signed

Authorizing Agent's  
Signature

Paul J. Rice  
Signature

Authorizing Agent's E-Mail Address:

price@freshdelmonte.com

**RETURN COMPLETED FORM TO:**

DEQ – Tidewater Regional Office  
Water Permits  
5636 Southern Boulevard  
Virginia Beach, VA 23462

Cc: (DEQ ECM FILE VPA01057)